

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-097-21039-0000

LEASE NAME NICHOLS

WELL NUMBER D-4

1650 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 20 TWP. 29S RGE. 18 (E) or (W)

COUNTY KIOWA

Date Well Completed 7/10/84

Plugging Commenced 1/4/98

Plugging Completed 1/9/98

LEASE OPERATOR MCNIC OIL & GAS MIDCONTINENT, INC

ADDRESS 5400 N. GRAND BLVD, STE 305, OKLA CITY, OK

PHONE# (405) 947-4322 OPERATORS LICENSE NO. 31577

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on N/A (date)

by _____ (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation LANSING Depth to Top 4346 Bottom 4490 T.D. 4874

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
LANSING	WATER	4346	4490	8 5/8	605'	0
DENNIS	WATER	4572	4582	5 1/2	4954'	2740'
HERTHA	WATER	4685	4689			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to _____ feet each set.

CIBP @4550' (W/2 SX CEMENT), CIBP @4475' (W/2 SX CEMENT ON TOP);
25 SX 4200 - 4300', 50 SX 1130 - 1230' (CIRC), 50 SX 530 - 630' (CIRC)
10 SX 40 - 4'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT'S CASING PULLERS License No. 269

Address 620 S. LINCOLN ST, LIBERAL, KS 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: MCNIC OIL & GAS MIDCONTINENT, INC

STATE OF KANSAS COUNTY OF SEWARD, ss.

HAROLD FRAULT (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Harold Frault

(Address) P O BOX 976, LIBERAL, KS 67905

SUBSCRIBED AND SWORN TO before me this 25TH day of JUNE, 1998

My Commission Expires: _____

Helen C. Berg
NOTARY PUBLIC, State of Kansas
HELEN C. BERG
Notary Public
My Appt. Exp 9-7-99