

LEASE NAME NICHOLS E

WELL NUMBER ONE

2310 Ft. from S/N Line of Section (circle one)

1650 Ft. from E/W Line of Section (circle one)

SPOT LOCATION C SW SE NW

SEC. 20 TWP. 29 S. RGE 18W (E) or (W)

COUNTY kiowa

Date Well Completed _____

Date Plugging Commenced April 21, 1999

Date Plugging Completed April 26, 1999

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

LEASE OPERATOR Herman L. Loeb

ADDRESS P.O. Box 524

CITY, STATE, ZIP Lawrenceville, Illinois 62439

PHONE# (618) 943-2211 OPERATORS LICENSE NO. 3273

Character of Well SWD
(Oil, Gas, D&A, (SWD) Input, Water Supply Well)

The plugging proposal was approved on April 22, 1999 (date)

by Steve Durrant (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation(s) Perfs 4572'-4573' Depth to Top PBTD 4835' Bottom _____ T.D. 4940'

Show depth and thickness of all water, oil and gas formations. Elevation 2247' GL

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
	SURFACE CASING	0'	612'	8 5/8"	612'	0'
	PRODUCTION CASING	0'	4939'	5 1/2"	4939'	811'

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

April 21, Set cast IRON B.P. at 2780', Dumped 2 sx Cement on top, Shot OFF AT 2700', Pipe would not pull out, Tried using Casing jacks - w/ 125,000# pull. No Movement
April 22, Found Free Point at 811', Shot pipe OFF, pulled 1jt of 5 1/2" out. April 26 - Pumped 40 sx cement, Pulled 4 jts of 5 1/2" & pumped 40 sx cement at 630', Pulled 16 jts 5 1/2" pipe and Filled w/ cement TO THE SURFACE.
Pulled Total of 21-5 1/2".

Name of Plugging Contractor Pratt Well Service Inc.

License No. 5893

Address P.O. Box 847 Pratt, KS 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Herman L. Loeb

STATE OF Kansas COUNTY OF Pratt, ss.

Stephen E. Hart % Pratt Well Service Inc. (Employee of Operator or (Operator) of above-described well, being first duty

sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Stephen E. Hart

(Address) P.O. 847 Pratt, Kansas 67124

SUBSCRIBED AND SWORN TO before me this 17th day of May, 1999

Kenneth W. Furgason
Notary Public

My Commission Expires:



RECEIVED
KANSAS CORPORATION COMMISSION
MAY 18 1999 1:22
5-18-99