

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Kiowa County, Sec. 15 Twp. 29 Rge. (E) 18 (W)

Location as "NE/CNW%SW%" or footage from lines C SE SE 1/4

Lease Owner Herman Geo. Kaiser, Oil Producer

Lease Name Corse Well No. 1

Office Address 909 Palace Building, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed April 8, 1960

Application for plugging filed April 8, 1960

Application for plugging approved April 8, 1960

Plugging commenced April 8, 1960

Plugging completed April 8, 1960

Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp, Jr.

Producing formation Depth to top Bottom Total Depth of Well 4951 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	433'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

MUDDED HOLE WITH HEAVY ROTARY MUD

TO 400 FT., SET PLUG AND CEMENTED WITH 20

SACKS CEMENT AND 1/3 SACK HULLS THROUGH DRILL

PIPE. MUDDED HOLE TO 35 FT. SET PLUG AND

CEMENTED WITH 1/3 SACKS HULLS AND 10 SACKS

CEMENT TO SURFACE.

RECEIVED
STATE CORPORATION COMMISSION
4-13-60
APR 13 1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Armer, Inc.

Address 709 Petroleum Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

L. C. Sponenberg (employee of contractor) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Sponenberg

L. C. Sponenberg (Address)

SUBSCRIBED AND SWORN TO before me this 12th day of April, 1960

My commission expires February 13, 1964

Rose Furey Notary Public.

15-097-00085-0000

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS


COMPANY **Herron Geo. Kaiser, Oil Producer**

SEC. **15** T. **29** R. **18W**
LOC. **C 62 DE 1/4**

FARM **Course** NO. **1**

TOTAL DEPTH **4951**
COMM. **3/21/60** COMP. **4/9/60**
SHOT OR TREATED
CONTRACTOR **Armer, Inc.**
ISSUED

COUNTY **Now**
KANSAS



CASING
20 10
15 8 **433'**
12 6
13 5

ELEVATION **2153 FT**
2155 MB

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

Top Soil & Shale	40°
Sand & Shale	70°
Shale & Shells	220°
Sand & Shale	300°
Shale & Shells	1075°
Anhydrite	1105°
Shale & Shells	1373°
Shale & Shells & Red Bed	1720°
Shale & Shells	2050°
Shale & Lime	2400°
Lime	2585°
Lime & Shale	2670°
Lime	2715°
Lime & Shale	3760°
Lime	4010°
Lime & Shale	4147°
Sandy Shale & Lime	4220°
Lime	4545°
Lime & Shale	4595°
Lime	4670°
Lime & Shale	4830°
Chert & Lime	4875°
Mississippi	4946°
Lime	4951°

RECEIVED
STATE COMMISSION
APR 13 1960
CONSERVATION DIVISION
Wichita, Kansas
4-13-60

Formation Tops:

Sample Tops:	
Heebner	4044° -1883
Toronto	4056° -1900
Douglas	4073° -1917
Brown Lime	4220° -2064
Lansing Kansas City	4233° -2077
Base Kansas City	4644° -2488
Marionton	4657° -2501
Cherokee	4763° -2607
Mississippi	4846° -2687
Lime	4932° -2776

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

ARMER, INC.
By L. C. Sponenberg
L. C. Sponenberg

STATE OF KANSAS)
) SS.
COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a Notary Public, in and for said County and State this 12th day of April, 1960.

My Commission expires 2/13/1961

Rose Furey
Rose Furey, Notary Public