


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section List

Kiowa County. Sec. 9 Twp. 29S Rge. 18W E/W
Location as "NE/CNW1/4SW1/4" or footage from lines
1450' FNL & 1950' FEL

Lease Owner Wells Energy Company
Lease Name Graves Well No. 1

Office Address Suite 454, 700 S. Colorado Bld., Denver,
Character of Well (Completed as Oil, Gas or Dry Hole) CO 80222
Dry Hole

Date Well completed August 5, 1979
Application for plugging filed Verbal Application 19
Application for plugging approved Verbal Approval 19
Plugging commenced August 5, 1979
Plugging completed August 5, 1979
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen
Producing formation Depth to top Bottom Total Depth of Well 5,033'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	451'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
 feet for each plug set.

Filled hole with heavy rotary mud from 5,033 ft. (rotary total depth) to
450 ft. Set plug at 450ft. and cemented with 50 sacks cement. Filled
hole with heavy rotary mud from 450 ft. to 40 ft. Set solid plug at
40 ft. and cemented to cellar with 12 sacks cement, 3 sacks cement in
rat hole

Plugging operations accomplished utilizing Halliburton Oil Well cementing
pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services
410 Union Center Building, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
Dean Britting, Agent ~~Notary Public~~ of owner ~~XXXXXXXXXXXXXXXXXXXX~~

of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
200 N. Main, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of August, 19 79

My commission expires July 25, 1982

Elsie Willison
Elsie Willison - Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

AUG 10 1979
8-10-79
CONSERVATION DIVISION
Wichita, Kansas

KANSAS DRILLERS LOG

COMPANY Wells Energy Company

SEC. 9 T. 29S R. 18W
LOC. 1450'FNL & 1950'FEL

FARM Graves NO. 1

COUNTY Kiowa

ROTARY TOTAL DEPTH 5,033'
COMM. July 24, 1979 COMP. August 5, 1979
CONTRACTOR H-30, Inc. (Rig #3)
ISSUED August 9, 1979

CASING

10 3/4"
8 5/8" 451' cemented w/300 sxs cement
5 1/2" didn't circulate lacked 3'
4 1/2"

ELEVATION

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	452'
Red Bed	1,000'
Shale	1,715'
Shale and Lime	3,169'
Lime and Shale	4,667'
Lime	4,905'
Lime and Shale	4,970'
Lime	4,995'
Lime and Shale	5,033'
Rotary Total Depth	5,033'

RECEIVED
STATE CORPORATION COMMISSION

AUG 10 1979
8-10-79
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Dean Britting
Dean Britting

State of Kansas }
County of Sedgwick } SS;

Subscribed and Sworn to before me a Notary Public in and for said county and state this 9th day of August, 1979.

Elsie Willison
Elsie Willison - Notary Public

