


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Kiowa County, Sec. 33 Twp. 29S Rge. 18 ~~XXE~~ (W)

Location as "NE/CNW%SW%" or footage from lines NE SW SE
Lease Owner Herman Geo. Kaiser
Lease Name Brown Well No. 1
Office Address 909 Palace Building, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 29, 1962
Application for plugging filed June 29, 1962
Application for plugging approved June 29, 1962
Plugging commenced June 29, 1962
Plugging completed June 29, 1962
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp, Jr.
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4,917 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	399'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 4,917 feet (RTD) to 360 feet.
Set bottom plug at 360 feet and cemented with 20 sacks cement.
Filled hole with heavy rotary mud to 35 feet. Set top plug and
cemented with 10 sacks cement, filling hole to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JUL 6 1962

CONSERVATION DIVISION
Wichita, Kansas

7-6-62

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor H-30, Inc.
Address 200 North Main Street, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. Priscilla M. Ismert contractor
(employee of ~~owner~~ or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Priscilla M. Ismert
200 North Main, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of July, 19 62

My commission expires December 3, 1964. Geraldine Hays Notary Public.

15-097-10163-0000


KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Herman Geo. Kaiser
FARM Brown NO. 1

33 29S 18W
SEC. NE SW SE R.
LOC.

TOTAL DEPTH 4,917'
COMM. 6-12-62 COMP. 6-23-62
SHOT OR TREATED
CONTRACTOR H-30, Inc.
ISSUED

COUNTY Kiowa
KANSAS



CASING
20 10 5/8" 300' com. w' 225 SX
15 8
12 6
13 5

GR 2120
DF 2131
ELEVATION KB 2134
PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Shale, Shells & Sand	375
Shale & Shells	400
Rat Hole	1049
Shale, Shells & Red Bed	1225
Anhydrite	1260
Shale, Red Bed & Shells	1740
Shale & Lime	2355
Lime & Shale	2555
Lime	2710
Lime & Shale	2990
Shale & Lime	3805
Lime & Shale	3865
Lime & Cherty Lime	3910
Lime	3985
Lime & Shale	4105
Shale & Lime	4235
Lime & Shale	4320
Lime	4725
Lime & Shale	4830
Lime	4868
Cherty Lime	4898
Mississippi	4917
Rotary T. D.	4917

RECEIVED
STATE CORPORATION COMMISSION

JUL 6 1962

CONSERVATION DIVISION
Wichita, Kansas

7-6-62

Electric Log Tops

Anhydrite Top	1225	+ 909
Anhydrite Base	1260	+ 874
Heebner	4070	-1936
Toronto	4090	-1956
Douglas	4105	-1971
Brown Lime	4248	-2114
Lansing	4260	-2126
Base, K. C.	4630	-2496
Marmaton	4656	-2522
Cherokee	4792	-2658
Mississippi	4884	-2750
Rotary T. D.	4917	-2783

I hereby certify that the above and foregoing is a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Priscilla M. Ismert
Priscilla M. Ismert

STATE OF KANSAS)
SS:
SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public in and for said county and state this 5th day of July, 1962.

Geraldine Hays
Geraldine Hays, Notary Public

My Commission Expires:
December 3, 1964.