


15-097-10105-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Kiowa County. Sec. 33 Twp. 29 Rge. (E) 18 (W)
Location as "NE/CNW/SW" or footage from lines SE/4 NE/4
Lease Owner Herman George Kaiser, Oil Producer
Lease Name Schmidt Well No. 2
Office Address Ellinwood, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced July 10 19 58
Plugging completed July 23 19 58
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. LacKamp
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	406	None
				5 1/2	4976	3756.22

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded hole to 4880' - dumped 5 sks cement - pumped hole full mud - set plug @ 300' - set 10' rock bridge - dumped 2 sks Cal Seal and 1 sk cement - bailed fluid down to plug - hole stayed dry - dumped 20 sks cement - mudded to 40' - set 10' rock bridge - dumped 10 sks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R & D Casing Pulling Company License # 236
Address Box 569 Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

I, W. J. Hall (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

(Address)

SUBSCRIBED AND SWORN to before me this 28 day of July 19 58

Notary Public.
STATE CORPORATION COMMISSION

My commission expires

PLUGGING
FILE SEC. 33 T. 29 R. 18W
BOOK PAGE 111 LINE 21

AUG 8 1958
CONSERVATION DIVISION
Wichita, Kansas

8-8-58

15-097-10105-0000

KANSAS GEOLOGICAL SOCIETY
WELL LOG BUREAU - KANSAS WELL SURVEY BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Herman Geo. Kaiser, Oil Producer
FARM Schmidt NO. 2

SEC. 33 T. 29 R. 18W
LOC. C SE NE 1/4

TOTAL DEPTH 4980'
COMM. 5/21/58 COMP. 6/10/58
SHOT OR TREATED
CONTRACTOR Armer, Inc.
ISSUED

COUNTY Kiowa
KANSAS

CASING
20 10
15 8 405'
12 6
13 5 4977'

ELEVATION 2162 K.B.
PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Shale & shells 525'
Shale, red bed & shells 1000'
Red Bed 1075'
Anhydrite 1105'
Red Bed & shale 1780'
Shale & shells 2285'
Shale & lime 2420'
Lime 2625'
Lime & shale 2730'
Lime 2780'
Lime & shale 3300'
Shale & shells 3445'
Shale & lime 3845'
Lime 4010'
Lime & shale 4284'
Lime 4375'
Shale & lime 4395'
Lime 4600'
Lime & shale 4630'
Lime 4870'
Lime & chat 4912'
Mississippi Chat 4929'
Chat 4932'
Cherty Lime 4944'
Cherty Lime & shale 4973'
Cherty Lime 4980'

Formation Tops:
Mississippi 4882'

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

Armer, Inc.
By *L. C. Sponenberg*
L. C. Sponenberg

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a notary public, in and for said County and State this 14 day of June, 1958.

My Commission Expires February 13, 1960.

R. P. Toney
Notary Public
JUL 1 1958
CONSERVATION DIVISION
Wichita Kansas

PLUGGING
FILE SEC 33 T 29 R 18W
BOOK PAGE 111 LINE 21

7-1-58