

15-097-10181-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

Kiowa County, Sec. 34 Twp. 29S Rge. XB 18 (W)

Location as "NE/CNW/SW" or footage from lines C NE NW

Lease Owner Sunray Mid-Continent Oil Company

Lease Name C. Schmidt Well No. A-2

Office Address Box 788, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 18 19 57

Application for plugging filed April 19 19 57

Application for plugging approved April 22 19 57


Plugging commenced April 18 19 57

Plugging completed April 18 19 57

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above
Section Flat

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4998 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	401	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy drilling mud to 350'. Set plug at 350' with 35 sacks cement from 350' to 245' through drill pipe. Filled hole with heavy drilling mud to 35'. Set sack of loose hulls and Hall plug at 35' with 15 sacks cement into bottom of cellar. Plugging completed.

Log attached.

(If additional description is necessary, use BACK of this sheet.)

Name of Plugging Contractor Halliburton Oil Well Cementing Company

Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

J. G. Ruby (employee of owner) or owner or operator of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. G. Ruby

Box 788, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of April, 19 57

My commission expires December 24, 1960

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC 34 Twp. 29 R. 18W
BOOK PAGE 7 LINE 41

APR 26 1957
CONSERVATION DIVISION
Wichita, Kansas
4-26-57

Sunray Mid-Continent Oil Company
Tulsa, Oklahoma

Tulsa, Oklahoma
April 23, 1957

CONTRACTOR: Stickle Drilling Company
Drilling Commenced: March 28, 1957
Drilling Completed: April 19, 1957

Schmidt A #2 NW/4 Section
34-29S-18W, Kiowa County,
Kansas.

DRILLERS LOG

Depth Figures Indicate Base of Formation:

Shale	225
Shale & Shells	1410
Shale	1570
Shale & Shells	1970
Shale & Lime	2225
Lime & Shale	2505
Lime	3010
Shale & Lime	3110
Lime & Shale	3295
Shale & Lime	3395
Lime & Shale	3940
Lime	4236
Shale	4330
Lime	4412
Lime & Chert & Shale	4442
Lime	4520
Lime & Shale	4533
Lime	4830
Lime & Shale	4910
Lime	4966
Lime & Shale	4998 TD

I, Frank E. Stickle hereby certify the above to be a true and complete Drillers Log of Sunray Mid-Continent Oil Company's Schmidt "A" #2 NW/4 Section 34-29S-18W, Kiowa County, Kansas.

Frank E. Stickle

Frank E. Stickle
CORPORATION COMMISSION

Lillian T. Bonham

Notary Public

February 13, 1960

My Commission Expires

PLUGGING		
FILE	SEC 34	29 R 18W
BOOK	PAGE 7	LINE 41

APR 26 1957
DIVISION
KANSAS

4-26-57