

15-097-10180-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

X			

Locate well correctly on above
Section Plat

Kiowa County, Sec. 34 Twp. 29 Rge. 18 (E) W (W)
 Location as "NE/CNW/SW" or footage from lines C NW NW
 Lease Owner Misco Supply Co.
 Lease Name Schmidt *A* Well No. # 1
 Office Address 257 N. Bdwy. ; Wichita, Kansas 67202
 Character of Well (completed as Oil, Gas or Dry Hole) _____
 Date well completed _____ 19____
 Application for plugging filed March 1972
 Application for plugging approved March 1972
 Plugging commenced April 5 1972
 Plugging completed April 20 1972
 Reason for abandonment of well or producing formation _____
 If a producing well is abandoned, date of last production _____ 19____
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Russell Biberstein
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	400	None
				5 1/2"	4945	3411

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

April 5, 1972 Plugged off bottom. Dumped sand to 3875'. Mixed and dumped 5 sx of cement.

April 20, 1972 Plugged off top. Set 10' rock bridge at 220'. Filled 8 5/8" surface casing from 220' to base of cellar with 3000 lb. P.S.I. ready-mix concrete.

RECEIVED
STATE CORPORATION COMMISSION

MAY 26 1972

5-26-72

CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor RUSS CASING PULLING, INC.
 Address P. O. Box 1082 ; Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Sedgewick, ss.
Thomas R. Spraul (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas R. Spraul
257 N. Broadway, Wichita, La. (Address)

May, 1972
Celeste Kinzie Notary Public.



Subscribed and sworn to before me this 25th day of May, 1972
prch 22, 1976

15-097-10180-0000

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

COPY

Company: SUNRAY MID-CONTINENT OIL CO.
Farm: C. Schmidt "A" No. 1

SEC. 34 T. 29 R. 18W
SE NW NW NW
590' fr WL 590' fr NL

Total Depth. 4946
Comm. 3-1-57 Comp. 3-22-57
Shot or Treated.
Contractor: Stickle Drilling Co.
Issued. 6-29-57

County Kiowa
KANSAS



CASING:
8 5/8 @ 400' w/ 400 sx cm t.
5 1/2 @ 4945' w/ 150 sx cmt.

Elevation. 2157 RB

Production: Flowed 81.05 BO &
5 BWPD

Figures Indicate Bottom of Formations.

top soil & clay	140
shale & shells	440
shale	1070
shale & shells	2290
lime	2400
lime & shale	2413
lime	2690
lime & shale	2830
lime	3014
lime & shale	3435
lime	3535
lime & shale	3695
lime	4015
lime & shale	4177
lime	4262
lime & shale	4361
lime	4400
lime & shale	4439
lime	4649
lime & shale	4668
lime, chert & shale	4710
lime	4741
lime & shale	4809
lime	4884
lime, shale & chert	4911
lime	4942
lime	4946
Total Depth	

TOPS:	
Lansing-KC	4260
Mississippi chert	4880
Mississippi lime	4932

RECEIVED
STATE CORPORATION COMMISSION
SEP 27 1971
CONSERVATION DIVISION
Wichita, Kansas

9-27-71