

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. MARKET, ROOM 2078
WICHITA, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

TYPE OR PRINT
NOTICE: Fill out Completely
and return to coms. div.
office within 30 days.

API NUMBER 15-097-21124-00-00
LEASE NAME Schmidt G
WELL NUMBER 1
4290 ft. from S Section Line
3630 ft. from E Section Line
SEC. 34 TWP. 29 RGE. 18 (E) or (W)
COUNTY Kiowa

LEASE OPERATOR Vincent Oil Corporation
ADDRESS 125 N. Market St., #1075, Wichita, KS 67202
PHONE # (316) 262-3573 OPERATORS LICENSE NO. 5004

Character of well Gas
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5/16/02 (date)
by Steve Durant (XCC District Agent's Name)

Is ACO-1 filed? yes if not, Is well log attached?

Producing Formation Marmaton Depth to Top 4782 Bottom 4787 T.D. 4999
Show depth and thickness of all water, oil and gas formations
OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Marmaton	Gas	4782	4787	8 5/8	477	none
				4 1/2	4998	3202

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set

Sand at 4730, baled 4 sacks cement. Shot pipe at 3429, 3202, came loose. Pull to 1200, pumped 10 sacks gel, 50 sacks cement. Pulled to 500, pump 50 sacks cement. Pull to 40' and ran 10 sacks cement.

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925
Address 401 West Main, Lyons, KS 67554

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vincent Oil Corporation

STATE OF KANSAS COUNTY OF SEDGWICK, ss.


Richard A. Hiebsch (Employee of Operator) or (Operator) of above - described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above - described well as filled that the same are true and correct, so help me God.

(Signature) Richard A. Hiebsch
(Address) 125 N. Market, Suite 1075
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me 29th day of May, 2002

Yolanda Eubanks
Notary Public

My commission Expires:



OR



RECEIVED

MAY 31 2002

KCC WICHITA

KCC Copy
COPY

SALES OFFICE:
105 S. Broadway
Suite #420
Wichita KS 67202
(316) 262-3699
(316) 262-5799 FAX

SALES & SERVICE OFFICE:
10244 NE Hwy 81
P.O. Box 8613
Pratt, KS 67124-8613
(316) 672-1201
(316) 672-5383 FAX

ACIDIZING - FRACTURING - CEMENTING

Invoice

Bill to: VINCENT OIL CORPORATION 125 N. Market, #1075 WICHITA, KS 67202	9050010	Invoice	Invoice Date	Order	Order Date
		205073	5/21/02	4771	5/17/02
	Service Description				
	Cement				
		Lease		Well	
		Schmidt		1	
AFE	CustomerRep	Treater	Well Type	Purchase Order	Terms
	Richard	T. Seba	Old Well		Net 30

<u>ID.</u>	<u>Description</u>	<u>UOM</u>	<u>Quantity</u>	<u>Unit Price</u>	<u>Price</u>
D203	60/40 POZ (COMMON)	SK	110	\$7.75	\$852.50
C321	CEMENT GEL	LB	1380	\$0.25	\$345.00
E107	CEMENT SERVICE CHARGE	SK	110	\$1.50	\$165.00 (T)
E100	HEAVY VEHICLE MILEAGE - 1 WAY	MI	37	\$3.00	\$111.00 (T)
E104	PROPPANT / BULK DELIV SERVICES/TON MILE, \$200 MIN	TM	176	\$1.25	\$220.00 (T)
R400	CEMENT PUMPER, PLUG & ABANDON (Workover Unit)	EA	1	\$650.00	\$650.00 (T)

Sub Total:	\$2,343.50
Discount:	\$773.56
Discount Sub Total:	\$1,569.94
Tax Rate: 5.90%	Taxes: \$45.30
(T) Taxable Item	Total: \$1,615.24

PLEASE REMIT TO Acid Services, LLC, Dept No 1131 , Tulsa, OK 74182

Accounts become past due the last day of the month following billing. Interest rate 1.5% per month (18% per year) on past due accounts.

RECEIVED

MAY 31 2002

TREATMENT REPORT



KCC WICHITA

Customer ID VINCENT OIL Corp	Date 5-17-02
Customer VINCENT OIL Corp	Lease No.
Lease SCHMIDT 'G'	Well # 1

Field Order # 4777	Station PRATT	Casing	Depth	County KTOWA	State KS
Type Job P.T.A. OLD WELL	Formation	Legal Description 31-29S-18W			

PIPE DATA		PERFORATING DATA		FLUID USED		TREATMENT RESUME		
Casing Size	Tubing Size	Shots/Ft		Acid		RATE	PRESS	ISIP
Depth	Depth	From	To	Pre Pad 110 SKS	Max			5 Min.
Volume	Volume	From	To	Pad 60/40 Pzr 6%GAL	Min			10 Min.
Max Press	Max Press	From	To	Frac 10 SKS GEL	Avg			15 Min.
Well Connection	Annulus Vol.	From	To		HHP Used			Annulus Pressure
Plug Depth	Packer Depth	From	To	Flush	Gas Volume			Total Load

Customer Representative K. HALE	Station Manager D. AVERY	Treater T. SEBA
------------------------------------	-----------------------------	--------------------

Time	Casing Pressure	Tubing Pressure	Bbls. Pumped	Rate	Service Log
12:30					CALLED OUT
15:00					ON LOC w/ TRK'S & SAFETY MNG
15:20	100		2.5	3	1 ST PLUG 1200' 50SKS MAX F PUMP 10 SKS GEL (BREAK CIRC)
15:37			14.1		MAX P PUMP 50 SKS CMT
16:00			9		DISP
16:10	100		5	2 1/2	2 ND PLUG 500' 50 SKS BREAK CIRC
16:10			14.1		MAX P PUMP 50 SKS CMT
16:20			3 1/2		DISP
16:20			2 5/8	1	3 RD PLUG 40' 10SKS CIRC CMT TO PIG
					JOB COMPLETE
					THANKS
					TODD



INVOICE NO.	Subject to Correction			FIELD ORDER 4771
Date 5-17-02	Lease SCHMIDT 'G'	Well # 1	Legal 34-295-18W	
Customer ID	County KIOWA	State KS	Station PRATT	

CHARGE	VINCENT OIL CORP	Depth	Formation	Shoe Joint
		Casing	Casing Depth	TD
		Customer Representative RICHARD	Treater	Job Type P.T.A. OLD WELL
				T. SEBA

AFE Number	PO Number	Materials Received by X <i>Jan Man</i>
------------	-----------	--

Product Code	QUANTITY	MATERIAL, EQUIPMENT and SERVICES USED	UNIT PRICE	AMOUNT	ACCOUNTING	
					CORRECTION	AMOUNT
D-203	110 SKI	60/40 P02	✓			
C-321	380 lbs	CEMENT GEL	✓			
C-321	1000 lbs	CEMENT GEL (ON SIDE)	✓			
E-107	110 SKI	CEMENT SERV. CHARGE		RECEIVED		
				MAY 21 2003		
				KCC, WICHITA		
E-100	37 mi	UNITS / way	MILES			
E-104	176 TM	TONS	MILES			
R-400	1 EA	EA. P.T.A.	PUMP CHARGE			
		DISCOUNTED PRICED		1,569.94		
		+ TAXES				

10244 NE Hiway 61 • P.O. Box 8613 • Pratt, KS 67124-8613 • Phone (620) 672-1201 • Fax (620) 672-5383 TOTAL