

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 23 1967
10-23-1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued September 27, 1967.

Operator's Full Name Graybol Oil Corporation 15-151-20498-0000

Complete Address: 2200 National Bank of Tulsa Bldg., Tulsa, Oklahoma 74103

Lease Name Welli Well No. # 1

Location C NE SW Sec. 7 Twp. 28 Rge. 13 (E) (W) W

County Pratt Total Depth 4556'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas 67530 License No. 49

Operation Completed: Hour 9:45AM Day 21st Month October Year 1967

The Above well was plugged as follows:

345' of 8 5/8" surface pipe, cemented with 250 sacks. 4556' of 4 1/2" long string,
cemented with 150 sacks. Plug back T.D. 4507'. Top perforation 4444'. Bottom of
the hole was sanded to 4400', and cemented with 4 sacks, through the dump bailer,
with cement from 4400' to 4350'. 3090' of 4 1/2" long string was recovered from the
hole. Bridge plug was pushed in fluid to 335', bridge plug and rock bridge from
335' to 325'. 6 sacks of cement was mixed in a barrel, and put on plug at 325',
through the dump bailer, and let set over-night. Next day hole was bailed dry, and
19 sacks of cement was added to the plug, with cement from 325' to 250'. Hole was
filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks,
with cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 10/23/67
INV. NO. 6541-u