

15-151-30029-0000

TP
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 13 1965

CONSERVATION DIVISION
Wichita, Kansas

9-13-1965

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Wm. Gruenerwald & Assoc., Inc.

Complete Address: Box 909, Colorado Springs, Colorado

Lease Name Hillard Well No. # 1

Location C NW SE Sec. 1 Twp. 28 Rge. 13 (E) (W) W

County Pratt Total Depth 4348'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Garvey Drilling Company

Address: R. R. # 2, Great Bend, Kansas License No.

Operation Completed: Hour 2:30 AM Day 10th Month Sept. Year 1965

The Above well was plugged as follows:

700' of 8 5/8" surface pipe, cemented with 650 sacks. Hole was filled
with drilling mud to 300', 1st cementing plug, bridged solid with dry
cement and hulls on fluid at 300', and cemented with 25 sacks. Hole
was filled with drilling mud to 40', 2nd cementing plug, bridged solid
with dry cement and hulls on fluid at 40', and cemented with 10 sacks
to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 9/13/65
INV. NO. 1791-W