

4 KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-095-01237-0000

RECEIVED
STATE CORPORATION COMMISSION

FEB 11 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name German Drilling Co.

Complete Address: 608 Petroleum Bldg., Wichita, Kansas

Lease Name Cooley Estate Well No. # 1

Location C NW/4 NW/4 Sec. 2 Twp. 28S Rge. 10 (E) W

County Kingman Total Depth 4489

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: German Drilling Co.

Address: 608 Petroleum Bldg., Wichita, Kansas License No.

Operation Completed: Hour 7:30PM Day 9th Month Feb. Year 1963

The Above well was plugged as follows:

245' of 8 5/8 " surface pipe circulated with 200 sacks cement.

Filled hole with heavy mud to 180', 1/2 sack hulls, 1st cementing plug,

cemented with 20 sacks. Filled hole with heavy mud to 40', 2nd cement-

ing plug, cemented with 10 sacks to base cellar. Rat hole bridged and

cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Chiving
Well Plugging Supervisor

DATE 2/11/63

INV. NO. 6554-u