

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 8 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Solar Oil Company 15-095-30007-0000

Complete Address: 1117 Union National Bldg., Wichita, Kansas

Lease Name Swander Well No. # 1

Location SE NW NW Sec. 29 Twp. 28 Rge. 9 (E) (W) W

County Kingman Total Depth 4202'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Sierra Petroleum Co., Inc.

Address: 1015 Wichita Plaza, Wichita, Kansas License No. _____

Operation Completed: Hour 10:00AM Day 6th Month Feb. Year 1965

The Above well was plugged as follows:

280' of 8 5/8" surface pipe, cement circulated with 200 sacks. Hole was
filled with drilling mud to 260', 1st cementing plug, bridged solid with
dry cement and hulls on fluid at 260', and cemented with 25 sacks. Hole
was filled with drilling mud to 40', 2nd cementing plug, bridged solid
with dry cement and hulls on fluid at 40', and cemented with 10 sacks
to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 2/8/65
INV. NO. 643-W

Signed: Archie Elving
Well Plugging Supervisor