

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-095-30063-0000

RECEIVED  
STATE CORPORATION COMMISSION  
6-28-66  
JUN 28 1966

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Don Rider of K & E Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Rider guarantees payment of the plugging fee.

Operator's full Name: Tomilson-Kathol, Inc.

Complete Address: 1125 Wichita Plaza Bldg., Wichita, Kansas

Lease Name: Prather Well No. # 4

Location: C NW SE NW Sec. 18 Twp. 28 Rge. 7 (E)(W) W

County Kingman Total Depth 4038' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Rider was instructed to plug the well as follows:

244' of 8 5/8" surface pipe, cement circulated. Fill hole with drilling mud to 240', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent