

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

WM. H. AVERY - Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-095-20052-6000

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed November 17, 1967.

Dear Sir:

Mr. Otto Beren of Donelson Drilling Co. has this
date requested permission to plug the following described well:

Mr. Beren guarantees payment of the plugging fee.

Operator's full Name: Beacon Resources Corporation

Complete Address: 412 Union Center Bldg., Wichita, Kansas 67202

Lease Name: Garnett Well No. # 1

Location: SW SW SW Sec. 35 Twp. 28 Rge. 6 (E)(W) W

County Kingman Total Depth 4085' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Beren was instructed to plug the well as follows:

281' of 8 5/8" surface pipe, cement circulated with 150 sacks. Fill
hole with drilling mud to 275', 1st cementing plug, bridge with 1/2 sack
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent