



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 24 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Clem Burton of Pickrell Drilling Co. has this date requested permission to plug the following described well:

Mr. Burton guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Co.

Complete Address: 705 4th National Bldg., Wichita, Kansas

Lease Name: Bock Well No. # 2

Location: C W/2 SW SW Sec. 7 Twp. 28 Rge. 7 (E) (W) W

County Kingman Total Depth 4085 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Burton was instructed to plug the well as follows:

210' of 8 5/8" surface pipe, cemented with 175 sacks. Fill hole with mud to 240', 1st cementing plug, bridge with hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, and cement with 10 sacks to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent