

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67702

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-129-21599-0000

Lease Name Hall

WELL NUMBER 1-155

330 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 5 TWP. 32S RGE. 40W or (W)

COUNTY Morton

Date well completed 1/27/00

Plugging Commenced 1/27/00

Plugging completed 1/27/00

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Pioneer Oil Company

Address RR 4 Box 142B Lawrenceville, IL 62439

Phone (618) 943-2227 OPERATORS LICENSE NO. 3273

Character of Well Oil

Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1/26/00 (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? yes If not, IS well log attached? yes

Producing Formation Dry hole Depth to Top _____ Bottom T.D. 5600'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Marmaton</u>	<u>Gas</u>	<u>4464</u>	<u>4501</u>	<u>8 5/8"</u>	<u>1600'</u>	<u>0'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set RIH w/ drill pipe to 3100'. Spot 110 sk plug from 3100' to 2650'. Pull DP to 1650', spot 55 sk plug from 1650' to 1425'. Pull DP to 450', spot 40 sk from 450' to 275'. POH w/ DP. Plug rathole w/ 10 sk. Plug mousehole w/ 10 sk. Total cement used 225 sk 40/60 pozmix w/ 6% gel.

Name of Plugging Contractor Big A Drilling License No. 31572

Address 100 South Main, Suite 508 Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pioneer Oil Company

STATE OF Indiana COUNTY OF Warrick '33.

George A. Payne (Employee of operator) or (Operator) of the of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the that the same are true and correct, so help me God. (Signature) George A. Payne

(Address) 7588 Marywood Drive Newburgh, IN 47630

Subscribed and sworn to before me this 9th day of March, 19 00

RECEIVED
 STATE CORPORATION COMMISSION

My commission expires: June 26, 01

Notary Public

Belinda M. Daniel
 Form CP-4

MAR 13 2000

CONSERVATION DIVISION
 Wichita, Kansas