

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

00197

API NUMBER 15-129-95004-0000

LEASE NAME Renshaw G.U.

WELL NUMBER A#1

SPOT LOCATION SW SW NE

SEC. 21 TWP. 32 RGE. 39 (E) or (W)

COUNTY Morton

Date Well Completed 8-51

Plugging Commenced 12-29-87

Plugging Completed 12-31-87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Amoco Production Co.

ADDRESS Box 432, Liberal, Ks. 67901

PHONE # (316) 624-6241 OPERATORS LICENSE NO. 5952

Character of Well Gas
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Ks.

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation Hugoton Depth to top 2453 bottom 2662 T.D. 2662

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface		0	605	10 3/4"	605'	0'
Production	Gas	0	2662	5 1/2"	2623'	1018

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Set CIBP @ 1280' w/2 sks. cement
Mud 1018' to 630' - Pump 50 sks. cement 630' to 530'
Mud 530' to 33' - Put Bridge and 20 sks. cement 33' to 3'
Cut off 10 3/4", 3' below ground level and cap

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497
Address Box F, Sublette, Ks. 67877

RECEIVED
STATE CORPORATION COMMISSION

STATE OF KANSAS COUNTY OF HASKELL, ss.

I, Edgar J. Eves (~~operator~~) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Edgar J. Eves

(Address) Box F, Sublette, Ks. 67877

SUBSCRIBED AND SWORN TO before me this 31 day of Dec., 1987

Sondra L. Eves
Notary Public

My Commission expires: 12-6-88

