

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 Finney State Office Building
 130 South Market, Rm 2078
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-189-22319-0000

LEASE NAME RHINEHART "B"

WELL NUMBER 3

4620 Ft. from S Section Line

1825 Ft. from E Section Line

SEC. 22 TWP. 32 RGE 39 (E) or (W)

COUNTY STEVENS

Date Well Completed 11-5-1999

Plugging Commenced 12/27/2000

Plugging Completed 1/6/2001

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/26/2000 (date)

by RICHARD LACEY (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached?

Producing Formation NONE Depth to Top Bottom T.D. 6020

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	1757'	NONE
				5-1/2"	6121'	2409'

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. MIRUPI. TOH W/TBG. MIX & PUMP 3 SXS HULLS & 25 SXS 60/40 PDZ CMT W/6% GEL TO 5168-4968'. DISPLACE. PULL FREE POINT & CUT OFF 5-1/2" @ 2409'. TOH W/5-1/2" CSG TO 1790'. PMP 50 SXS CMT FROM 1640-1790'. TOH W/5-1/2" CSG TO 700'. PMP 40 SXS CMT FROM 600-700'. TOH TO 40' & PMP 10 SXS CMT 40' TO SURFACE. TOH W/REMAINING 5-1/2" CSG. CUT OFF AND CAP 8-5/8" CSG 4' BELOW GL. PERMANENTLY INSCRIBE WELL NAME, NUMBER AND DATE PLUGGED ON CAP. RDMO. RESTORE LOCATION.

(If additional description is necessary, use BACK of this form.)

RECEIVED
 KANSAS CORPORATION COMMISSION

Name of Plugging Contractor SARGENTS CASING PULLING SERVICE License No. 6547

Address P.O. BOX 506, LIBERAL, KANSAS 67905-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION CONSERVATION DIVISION WICHITA, KS

STATE OF KANSAS COUNTY OF SEWARD, ss.

L. MARC HARVEY (Employee of Operator) or (Operator) of above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) L. Marc Harvey 1-9-01

L. MARC HARVEY, ENGINEERING TECHNICIAN III
 (Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 9th day of January, 2001

Shirley J. Childers
 Notary Public

My Commission Expires: 11/14/02



Form CP-4
 Revised 03-88