

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-129-10136
LEASE NAME Tillett G.U.
WELL NUMBER B#1
SPOT LOCATION SW NE
SEC. 19 TWP. 32 RGE. 39 (X) or (W)
COUNTY Morton
Date Well Completed 3-61
Plugging Commenced 12-18-86
Plugging Completed 12-22-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Amoco Production Co.
ADDRESS P. O. Box 432 Liberal, KS 67901

PHONE # (316) 624-6241 OPERATORS LICENSE NO. 5952

Character of Well Gas
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Ks.

Is ACO-1 filed? yes If not, Is well log attached?

Producing formation Morrow Depth to top 5724 bottom 5726 T.D. 6050
5816 5818
5830 5832

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Morrow	Gas	5724	5726	8 5/8"	710'	0' Surface
		5816	5818	4 1/2"	5924'	780' Production
		5830	5832			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Set CIBP @ 5680' and capped w/2 sks. cement. Displaced w/mud to 780' - Pumped 75 sks. cement 780' to 650'. Displaced w/mud 650' to 40' - put bridge and 15 sks. cement 40' to 5'. Cut off 8 5/8", 5' below ground level and weld plate on same.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497
Address Box F, Sublette, Ks. 67877

STATE OF Kansas COUNTY OF Haskell, ss.

I, Edgar J. Eves (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Edgar J. Eves
(Address) Box F, Sublette, Ks. 67877

SUBSCRIBED AND SWORN TO before me this 22 day of Dec., 1986

My Commission expires: 12-6-88

Sondra L. Eves
Notary Public