

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER N/A 15-151-20532-0008 (of this well) 7/87
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Petrie Exploration OPERATORS LICENSE NO. 03055

ADDRESS Rt. #1, Pratt, Kansas 67124 PHONE # (316) 672-6236

LEASE (FARM) Hamilton WELL NO. 1 WELL LOCATION SW-NE-NW COUNTY Pratt

SEC. 21 TWP. 28S RGE. 13 (E) or (W) TOTAL DEPTH 3250 PLUG BACK TD 3210

Check One:

OIL WELL _____ GAS WELL X D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8 SET AT 205 CEMENTED WITH NA SACKS _____

CASING SIZE 4 1/2 SET AT 3250 CEMENTED WITH NA SACKS _____

PERFORATED AT 3125-3128

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL _____

Per KCC

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? no
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN ASAP

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Stanley Petrie PHONE # (316) 672-6236

ADDRESS Rt. #1, Pratt, Kansas 67124

PLUGGING CONTRACTOR Great Bend Casing Pullers, Inc. LICENSE NO. 4635 CP 9/87

ADDRESS Box 768, Great Bend, Kansas 67530 PHONE # (316) 793-9711

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Randy P. Wagner

(Operator or Agent)
STATE CORPORATION COMMISSION

DATE: 2-6-87

FEB 9 1987

CONSERVATION DIVISION
Wichita, Kansas

C. E. (ED) LEITH
OPERATIONS
427 UNION CENTER BLDG.
WICHITA, KANSAS 67202
TELEPHONE 316-265-3491

15-151-20532-0000

PETRIE EXPLORATION CO., INC.
P. O. Box 327
Pratt, Kansas 67124

HAMILTON LEASE WELL NO. 1
SW NE NW Sec. 21-28S-13W
Pratt County, Kansas

COMPLETION RECORD

SUMMARY:

Plug Back Total Depth 3210'
Casing Perforations: 3125' - 3128'
Stimulation: 500 gal. 15% MCA Acid
Tubing: 3128' - 2-3/8"OD
Seating Nipple- 2-3/8" x 12" (Open End)

DETAIL:

9-7-78

Move in and rig up double drum well service unit - Unload Tubing - Ran Gamma-Collar Correlation Log - Ran 101 jts. 3128' - 2-3/8"OD EUE 8rd. SH tubing w/ 2-3/8" x 12" Std. Seating Nipple - Open End - Circulate hole w/ 2% KCL water - Spot 100 gal. acetic Acid on bottom - Space tubing - Perforate 4 1/2" casing 3125'-3128' w/ 10 thru tubing jets - Respace tubing - shut in on night.

9-8-78

Set overnight - casing & tubing full - Swab down - no shows - Acidize w/ 500 gal. 15% MCA Acid - = Stage pressure to 550# - break & feed - Increase rate to 1-BPM = pressure breaking during displacement to Zero - Swab 1-pull off bottom thru tubing - start flow - Flow & clean up load water to pit = Flow test CP 850# - TP 850# - Rate 2,341 MCF/D gas - No fluid - Stable rate and pressures - Shut in - tear down tools.

STATE CORPORATION COMMISSION

FEB 9 1987

CONSERVATION DIVISION
Wichita, Kansas

State of Kansas



JOHN CARLIN
MICHAEL LENNEN
MARGALEE WRIGHT
KEITH R. HENLEY
JUDITH A. McCONNELL
BRIAN J. MOLINE

Governor
Chairman
Commissioner
Commissioner
Executive Secretary
General Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Dorby Building
202 West 1st Street
WICHITA, KANSAS 67202-1286

Extension
THIS NOTICE
JUN 10 '87
EXPIRES
30-Days

THIS NOTICE
~~MAY 10 '87~~
EXPIRES

15-151-20532-0000

February 10, 1987
WELL PLUGGING NOTICE

Hamilton #1
SW NE NW
Sec. 21-28S-13W
Pratt County

Petrie Exploration
Route 1
Pratt, KS 67124

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

Jack McCord, Director

Please contact the district office to review your suggested method of plugging

DIST. #1 302 West McArtor, Dodge City, KS 67801 (316) 225-6760

five days prior to plugging the well (KAR-82-3-113).