

RECEIVED
STATE CORPORATION COMMISSION

4-20-82

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION

APR 20 1982

CONSERVATION DIVISION AGENT REPORT

CONSERVATION DIVISION
Wichita, Kansas

API Number 15-097-20873-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Raymond Oil Co. Inc.

Complete Address One main Place, Suite 900, Wichita, Kansas

Lease Name Chadd Well No. 1

Location B-5/2-NH#4 Sec. 35 Twp. 29 Rge. 18 (East)(West)

County Neosho Total Depth 5050'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Murphy Drilling Co.

Address 617 Union Center Bldg, Wichita, Kansas 67202 License No. _____

Operation Completed: Hour: 6:45 PM Day: 15 Month: April Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

The anhydrite was topped at 1290'. 1st plug at 1210' with 60 sbp of cement. 2nd plug push rubber plug to 620' and pumped 35 sbp of cement on top of it. 3rd plug 40' to 0' on solid bridge with 10 sbp of cement. Then circulated 10 sbp of cement in rat hole & 5 sbp of cement in mouse hole. The cement was pumped through drill pipe with hole full of heavy mud. The plugging was accomplished by Allied Cementing. Cement used was Commodity with 3 Dell & 2% CC.

Amount of Surface Casing: 650' of 8 3/8" cement circulated

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luther
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: _____
Conservation Division Agent

INVOICED

DATE 4-28-82

INV. NO. 88-W