

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name Raymond Oil Co., Inc.

Complete Address 200 W. Douglas, Suite 800, Wichita, Ks. 67202

Lease Name Fralick Well No. 1

Location SW NE SE SW Sec. 5 Twp. 29 Rge. 19 (E) (W) X

County Kiowa Total Depth 5080

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176 Chase, Kansas. 67524 License No. 683

Operation Completed: Hour 1:30 Pm. Day 25 Month 5 Year 1979

The above well was plugged as follows:

625' 8 5/8" casing w/375 sax cement. 5 1/2" casing set at 5074' w/150
sax cement.& 50 sax latex.6' open hole-Sand back to 5050' top sand w/
5 sax mixed cement w/ dump bailer. Pull 3350' 5 1/2" casing. Build
bridge at 425' back to 400'-Fill 8 5/8" casing w/ 6 yard Ready Mix
Cement. Kingman Ready Mix. Kingman, Kansas.

RECEIVED
STATE CORPORATION COMMISSION
5-29-79

MAY 29 1979

I hereby certify that the above well was plugged as herein stated.

INVOICED CONSERVATION DIVISION
Wichita, Kansas

Signed: *[Signature]*
Well Plugging Supervisor

DATE 5-30-79

INV. NO. 9714-W