



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 15 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Raymond Oil Co Inc

Complete Address 200 W. Douglas Wichita, KS

Lease Name Porter Well No. 1

Location C. SE/SE Sec. 5 Twp. 29 Rge. 19 (E) (W) W

County Kiowa Total Depth 5116

Abandoned Oil Well Gas Well Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Co Inc

Address Box 405 Chase, KS License No. 436

Operation Completed: Hour 9:00 AM Day 11 Month 1 Year 1974

The above well was plugged as follows:

610 ft 8 5/8 surface cemented with 475 sacks. 5114 ft 5 1/2 long string
cemented with 175 sacks. Top perf. 5006 ft. Sand to 4550 ft, 5
sacks cement with bailer. Pulled 2966 ft 5 1/2. Set 10 ft rock bridge
at 210 ft with 25 sacks cement. Mud to 40 ft, 10 ft rock bridge ,
10 sacks cement to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 1/16/74

INV. NO. 8410-LU