

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 12 1972

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Misco Supply Co.
Complete Address 257 N Broadway, Wichita, Ks
Lease Name Keith Brown Well No. 5
Location C1-SW-NW Sec. 33 Twp. 29 Rge. 18 (E) (W)
County Kiowa Total Depth 5010
Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____
Plugging Contractor Ralph Comstock Pipe Pulling Co Inc.
Address Stafford, Ks License No. 490
Operation Completed: Hour 4:00 PM Day 8 Month 6 Year 1972

The above well was plugged as follows:

404 ft. 8 5/8 in. cemented with 250 lbs.
5009 ft. 5 1/2 in. long string cemented with 150 lbs.
Top pipe 4954 ft. ~~sent to~~ Push plug to
4500 ft. sand to 4450 ft. 5 in cement
with bailer. Pulled 3450 ft of 5 1/2 in. set 10 ft
rock bridge at 220 ft. Fill hole with
3yds of redmud to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: A. Russell Bivertain
Well Plugging Supervisor

INVOICED
DATE 6-13-72
INV. NO. 5852-W