

KANSAS

Handwritten mark

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 20 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Misco Industries

Complete Address Misco Bldg. Wichita, Ks

Lease Name Keith Brown Well No. 3

Location NE/SW/NE Sec 33 Twp. 29 Rge. 18 (E) W

County Kiowa Total Depth 4995

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Ralph Comstock Casing Pulling Inc.

Address Stafford, Ks License No. 490

Operation Completed: Hour 11:00 AM Day 19 Month 10 Year 1971

The above well was plugged as follows:

414 ft 8 5/8 surface pipe cemented with 250 sacks. 4994 ft 5 1/2 long
string cemented with 150 sacks. Pump plug to 4500 ft. Sand back
to 4495 ft, 5 sacks cement with bailer. Pulled 3100 ft 5 1/2. Set
20 ft rock bridge at 260 ft. Fill hole with 4 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: J. Russell Bihlerstein
Well Plugging Supervisor

DATE 10/20/71
INV. NO. 4511-W