

KANSAS

AP

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 18 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Misco Industries

Complete Address Misco Bldg. Wichita, Ks

Lease Name Keith Brown Well No. 1

Location C NW/NE Sec 33 Twp. 29 Rge. 18 (E) (W) W

County Kiowa Total Depth 4980

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Ralph Comstock Casing Pulling

Address Stafford, KS License No. 490

Operation Completed: Hour 5:00 PM Day 13 Month 10 Year 1971

The above well was plugged as follows:

410 ft 8 5/8 surface pipe cemented with 250 sacks. 4980 ft 5 1/2 long
string cemented with 150 sacks. Pump plug to 4500 ft. Sand back
4475 ft, 5 sacks cement with bailer. Pulled 2850 ft 5 1/2. Set 20 ft
rock bridge at 260 ft. Fill hole with 4 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: *A. Russell Bickert*
Well Plugging Supervisor

INVOICED

DATE 10-18-71

INV. NO. 4484-W