

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
7-2-62 JUL 2 1962
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Kaiser-Francis Oil Co.
Complete Address: 905 Palace Bldg Tulsa, Oklahoma
Lease Name Brown Well No. 1
Location NE SW SE 33 29 18 W Sec. 33 Twp. 29 Rge. - (E) (W) 18
County Kiowa Total Depth 4917
Abandoned Oil Well Gas Well Input Well SWD Well D & A L
Other well as hereafter indicated:

Plugging Contractor: H-30, Incorporated
Address: 200 N. main Wichita, Kans. License No. rotary
Operation Completed: Hour 1³⁰ pm Day 29 Month June Year 1962

The Above well was plugged as follows:

399 ft 8 5/8" surface pipe - Hole filled with heavy drilling mud to 360 ft - 1/4 sack hells and cementing plug - 20 sacks cement through drill pipe - filled to 40 ft with heavy drilling mud - 1/4 sack hells and cementing plug - 10 sacks cement to bottom of cellar - bridged rat hole, with 2 sacks

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 9/3/62
INV. NO. 5296-w

Signed: Herman Justus
Well Plugging Supervisor