

KANSAS

AL STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 3 1972

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Misco Supply Co.

Complete Address 257 N Broadway Wichita, Ks

Lease Name Brown "B" Well No. 1

Location C NW/SW Sec. 33 Twp. 29 Rge. 18 (E) (W) W

County Kiowa Total Depth 4991

Abandoned Oil Well Gas Well Input Well SWD Well X D & A

Other well as hereafter indicated

Plugging Contractor Ralph Comstock Pipe Pulling Inc.

Address Stafford, Ks License No. 490

Operation Completed: Hour 4:00 PM Day 29 Month 6 Year 1972

The above well was plugged as follows:

356 ft 8 5/8 surface pipe cemented with 250 sacks. 4343 ft 5 1/2 long

string cemented with 125 sacks. Top perf. 4286 ft. Sand to 4150 ft,

5 sacks cement with bailer. Pulled 3030 ft 5 1/2. Set 10 ft rock bridge

at 220 ft. Fill hole with 3 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: *Russell B. Senter*
Well Plugging Supervisor

INVOICED

DATE 7/5/72

INV. NO. 5993-W