

15-097-10107-0000

Form CP-3
Rev. 6-4-68

KANSAS

VP
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 11 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Misco Industries Inc
Complete Address 257 N Broadway Wichita, KS
Lease Name Williams Well No. 1
Location C SW/NE Sec. 34 Twp. 29 Rge. 18(E) (W) W
County Kiowa Total Depth 4990
Abandoned Oil Well Gas Well X Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Glenn Pipe Pulling Co.
Address Box 156 Ellinwood, KS License No. 686
Operation Completed: Hour 6:30 PM Day 9 Month 5 Year 1973

The above well was plugged as follows:

410 ft 8 5/8 surface cemented with 225 sacks. 4989 ft 5 1/2 long string
cemented with 150 sacks. Top perf. 4920 ft. Sand to 4900 ft, 5 sacks
cement with bailer. Pulled 3400 ft 5 1/2. Set 10 ft rock bridge at
350 ft. Fill hole with 5 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *L. Russell Bikerstein*
Well Plugging Supervisor

DATE 5/11/73
INV. NO. 7349-W