

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 207B
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-129-10051 COB-00

LEASE NAME Jackson

WELL NUMBER 1-14
1320 Ft. from S Section Line
1320 Ft. from E Section Line

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

SEC. 14 TWP. 32 RGE. 42 (E) or (W)

COUNTY Morton

LEASE OPERATOR Nadel and Gussman, LLC

ADDRESS 3200 First Place Tower Tulsa OK 74103

PHONE (918) 583 3333 OPERATORS LICENSE NO. 32638

Date Well Completed _____

Character of Well Gas

Plugging Commenced 12-20-00

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12-21-00

The plugging proposal was approved on 12-19-00 (date)

by Kevin Strube (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? YES

Producing Formation Tapeka Depth to Top 2808' Bottom 3168' T.O. 3375'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				<u>8 5/8</u>	<u>626</u>	<u>-</u>
				<u>5 1/2</u>	<u>3290</u>	<u>660</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each section.

Rosel dumped 2 5x cmt. on sand fill @ 2572. Mixed 2 5x hulls & 25 5x plug down 5 1/2 from 1100 to 900. Shot 5 1/2 loose @ 660 Circ. hole w/mud & mixed 50 5x plug from 660 to 510. 10 5x 40 to 0. Cut off & capped 8 5/8 3 ft. below C.L.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515 STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Nadel and Gussman, L.L.C. JAN 16 2001

STATE OF Oklahoma COUNTY OF Tulsa CONSERVATION DIVISION
Wichita, Kansas

James R. Piland

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) James R. Piland

(Address) 3200 First Place Tower, Tulsa, OK 74103



SUBSCRIBED AND SWORN TO before me this 11th day of January, 2001

KATHY GARROW
Creek County

Commission Expires 08/01/2003

My Commission Expires: 8-1-03

Kathy Garrow
Notary Public

**SARGENT AND HORTON
PLUGGING, INC.**

Route 1, Box 49BA
Tyrone, OK 73951-9731

No 2083

DAILY REPORT

DATE 12-19-00 FROM 1:00 TO 5:00

COMPANY

FARM NO.

Nadel and Gussman Jackson 144

HOURS WORKED

NAME

4

D. Horton

4

J. Schoolcraft

4

A. Pineda

CONTRACTOR'S TIME _____ COMPANY'S TIME 4

REMARKS: Rig up pole. Dig cellar.
Split wellhead off of 5 1/2.

**SARGENT AND HORTON
PLUGGING, INC.**

Route 1, Box 49BA
Tyrone, OK 73951-9731

No. 2084

DAILY REPORT

DATE 12-20-00 FROM 7⁰⁰ TO 5⁰⁰

COMPANY

FARM NO.

Nadel and Gussman Jackson 1-14

HOURS WORKED

NAME

10

D.H.

10

J.S.

10

A.P.

CONTRACTOR'S TIME 2 COMPANY'S TIME 8

REMARKS: Rosel dumped 2 sx cmt. on sand
fill @ 2572. Rig up jacks & pump
truck. Mixed 2 sx hulls & 25 sx
cmt. plug from 1100 to 900. Shot 5 1/2
loose @ 660. Circ. hole w/ mud &
mixed 50 sx from 660 to 510.
Pull to 40. 10 sx plug from 40 to 0.
21 jts in all.

**SARGENT AND HORTON
PLUGGING, INC.**

Route 1, Box 49BA
Tyrone, OK 73951-9731

No. 2085

DAILY REPORT

DATE 12-21-00 FROM 7⁰⁰ TO 11⁰⁰

COMPANY

FARM NO.

Nadel & Gussman Jackson 1-14

HOURS WORKED

NAME

<u>5</u>	<u>D.H.</u>
<u>5</u>	<u>J.S.</u>
<u>5</u>	<u>A.P.</u>

CONTRACTOR'S TIME _____ COMPANY'S TIME 4

REMARKS: Load out jacks. Cut off &
capped 8⁵/₈ 3 ft. below G.L.
Tore down & tally pipe.