

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-129-21661-00-00

LEASE NAME Heyen

WELL NUMBER 1-16

1980 Ft. from (S) Section Line

1320 Ft. from (E) Section Line

SEC. 16 TWP. 32S RGE. 42W (E) or (W)

COUNTY Morton

Date Well Completed 02/07/02

Plugging Commenced 02/07/02

Plugging Completed 02/07/02

RECEIVED

FEB 20 2002

KCC WICHITA

LEASE OPERATOR Dominion Oklahoma Texas E&P, Inc.

ADDRESS 14000 Quail Springs Parkway - Suite 600 - Okla. City, OK 73134

PHONE#(405) 748-2725 OPERATORS LICENSE NO. 32971

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 02/07/02 (date)

by Richard Lacey at Dodge City District Office (KCC District Agent's Name)

Is ACO-1 filed? Yes if not, is well log attached?

Producing Formation NA Depth to Top Bottom T.D. 5215'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		Surface	1477'	8-5/8"	1477'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set 100 sx plug @ 3100' (Base of Council Grove), 50 sx. plug @ 1500'. 50-sx. @ 740'. 10 sx. @ 34'. 15-sx in rat hole & 10 sx in mouse hole.

Total 235 sx. 40/60 Poz with 6% gel.

Name of Plugging Contractor Halliburton Services License No.

Address 1100 W. Pancake, Liberal, KS 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Dominion Oklahoma Texas E&P, Inc.


STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Dominion Oklahoma Texas E&P, Inc. (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Lenna Sawyer

(Address) 14000 Quail Springs Parkway - Okla. City, OK 73134




SUBSCRIBED AND SWORN TO before me this 15th day of February, 19 2002

(Signature) Lorie A. Benford
Notary Public

Commission Expires: 9/1/05

Handwritten initials 'OL'

 HALLIBURTON		JOB LOG		TICKET # 1740762	TICKET DATE 02/07/02
REGION North America Land		NWA / COUNTRY Mid Continent		BDA / STATE KS	COUNTY MORTON
MBU ID / EMPL # MCL10103		H.E.S. EMPLOYER NAME Shaun Fredrick		PSL DEPARTMENT Cementing Services	
LOCATION Liberal		COMPANY DOMINION		CUSTOMER REP / PHONE DARRELL TOEWS/405-206-6742	
TICKET AMOUNT \$6,809.26		WELL TYPE 01		APULUM # 15-129-21661	
WELL LOCATION LAND		DEPARTMENT Cement		JOB PURPOSE CODE Cement Plug to Abandon	
LEASE NAME HEYEN		Well No. 1-16	SEC / TWP / RNG 16-32S-42W	HES FACILITY (CLOSEST TO WELL #) LIBERAL	

HES EMP NAME/EMP # (EXPOSURE HOURS)	HRS	HES EMP NAME/EMP # (EXPOSURE HOURS)	HRS	HES EMP NAME/EMP # (EXPOSURE HOURS)	HRS	HES EMP NAME/EMP # (EXPOSURE HOURS)	HRS
Fredrick, S - 106114							
Davis, T - 106304							
Kirby, K - 105942							
Schawo, N - 222552							

Chart No.	Time	Rate (BPM)	Volume (BBL/GAL)	Rate		Press. (PSI)		Job Description / Remarks
				Hz	Gal	GS	TL	
	1330							CALLED OUT FOR JOB
	1330							ON LOCATION LAYING DOWN COLLARS
	1600							START IN HOLE W/ D.P.
								1ST PLUG @ 3100 (Base of Council Grove)
	1757					1200		PSI TEST LINES
	1758	6.0	10.0			250		PUMP H2O SPACER
	1800	6.0	27.0			200		PUMP 100SX PREM 60/40 @ 13.2
	1805	6.0	33.5			276		PUMP DISPLACEMENT
	1812							SHUT DOWN PULL DP
								2ND PLUG @ 1500FT
	1919	6.0	10.0			120		PUMP H2O SPACER
	1921	6.0	13.5			250		PUMP 50 SKS 60/40 @ 13.2
	1925	6.0	14.0			170		PUMP DISPLACEMENT
	1927							SHUT DOWN PULL DP
								3RD PLUG @ 740 FT
	1955	6.0	40.0					PUMP H2O SPACER
	2002	6.0	13.5					PUMP 50 SKS 60/40 @ 13.2
	2003	6.0	8.0					PUMP DISPLACEMENT
	2006							SHUT DOWN PULL DP
								4TH PLUG @ 34 FT
	2100		5.0					PUMP H2O SPACER
	2105		3.0					PUMP 10 SKS 60/40 @ 13.2
	2110		4.0					PUMP 15 SKS 60/40 @ 13.2 RAT HOLE
	2115		3.0					PUMP 10 SKS 60/40 @ 13.2 MOUSE HOLE
	2130							JOB COMPLETE

RECEIVED
FEB 20 2002
KCG WICHITA