

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE NAME Stoops

WELL NUMBER 1-18

1320 Ft. from S Section Line

1320 Ft. from ^W Section Line

SEC. 18 TWP. 32 RGE. 42 (W)

COUNTY Morton

Date Well Completed N/A

Plugging Commenced 12-14-00

Plugging Completed 12-15-00

LEASE OPERATOR Nadel and Gussman LLC

ADDRESS 3200 First Place Tower, Tulsa OK 74103

PHONE (918) 583 3333 OPERATORS LICENSE NO. 32638

Character of Well Leas

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-14-00 (date)

by Scott Alberg (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? Yes

Producing Formation Topeka Depth to Top 2956' Bottom 3188' T.D. 3330

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				<u>8 5/8</u>	<u>634</u>	
				<u>5 1/2</u>	<u>3230</u>	<u>803</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each so
CIBP + 2 SX 2700 Load hole w/mud & mixed recovered 803 5 1/2
Circ. hole w/mud & mixed 25 SX @ 803. 50 SX 650 to 500
10 SX 40 to 0 Cut off & capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515 **RECEIVED**
 STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Nadel and Gussman, L.L.C. **JAN 16 2001**

STATE OF Oklahoma COUNTY OF Tulsa **55-1-16-01**
 CONSERVATION DIVISION

James R. Piland (Employee of Operator) (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 3200 First Place Tower, Tulsa, OK 74103



SWORN TO before me this 11th day of January, 2001

[Signature]
 Notary Public

My Commission Expires: 8-1-03

**SARGENT AND HORTON
PLUGGING, INC.**

Route 1, Box 49BA
Tyrone, OK 73951-9731

No. 2077

DAILY REPORT

DATE 12-13-00 FROM 1:00 TO 4:00

COMPANY

FARM NO.

Nadel and Gussman LLC Steeps 1-18

HOURS WORKED

NAME

<u>3</u>	<u>D. Horton</u>
<u>3</u>	<u>J. Schoolcraft</u>
<u>3</u>	<u>A. Pineda</u>

CONTRACTOR'S TIME _____ COMPANY'S TIME 3

REMARKS: Move on from Tyrone OK.

**SARGENT AND HORTON
PLUGGING, INC.**

Route 1, Box 49BA
Tyrone, OK 73951-9731

No. 2078

DAILY REPORT

DATE 12-14-00 FROM 7⁰⁰ TO 6⁰⁰

COMPANY

FARM NO.

Nadel & Gussman Stoops 1-18

HOURS WORKED

NAME

<u>11</u>	<u>D.H.</u>
<u>11</u>	<u>J.S.</u>
<u>11</u>	<u>A.P.</u>

CONTRACTOR'S TIME 3 COMPANY'S TIME 8

REMARKS: Rig up pole. Backhoe dug
cellar & pit. Removed tubing head
& cut slips out of casing head.
Load hole w/mud. Rig up jacks. Shot
5½ @ 1600 & worked pipe. Shot
@ 803. Circ. hole w/mud & mixed
25 sx plug from 800 to 725. Pull to
650 & mixed 50 sx 650 to 500.
Pull 400 ft.

**SARGENT AND HORTON
PLUGGING, INC.**

Route 1, Box 49BA
Tyrone, OK 73951-9731

No. 2079

DAILY REPORT

DATE 12-15-00 FROM 7⁰⁰ TO 1⁰⁰

COMPANY

FARM NO.

N & G

Stoops 1-18

HOURS WORKED

NAME

6

D.H.

6

J.S.

6

A.P.

CONTRACTOR'S TIME 1 COMPANY'S TIME 5

REMARKS: Pull 5 1/2 to 40. Mixed 10 sk
40 to 0. 26 jts in all. Load out
jacks. Cut off & capped 8 5/8 3 ft.
below G.L. Tore down & tally pipe.