

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-129-21,029-0000

LEASE NAME ARNOLD "B"

TYPE OR PRINT

NOTICE: Fill out **completely**
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

660 Ft. from S Section Line

3300 Ft. from E Section Line

LEASE OPERATOR Anadarko Petroleum Corporation

SEC. 33 TWP. 32S RGE. 42 (W)

ADDRESS P.O. Box 351, Liberal, Kansas 67905

COUNTY Morton

PHONE#(316) 624-6253 OPERATORS LICENSE NO. 4549

Date Well Completed 2/23/90

Character of Well D & A

Plugging Commenced 2/22/90

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2/23/90

The plugging proposal was approved on 2/22/90 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation NA Depth to Top _____ Bottom T.D. 5234

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	1351	8 5/8	1351	0
		2060	5060	4 1/2	5060	3000

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Spot 20 sxs cmt @ perfs 4793-4593. Shot off csg @ 3000'. Pull 4 1/2 csg to 1370. Spot 55 sxs cmt from 1370 to 1270. Pull csg. to 600'. Spot 25 sxs cmt from 750-600. TOH w/csg, Spot 10 sxs cmt from 40-0. Cut off 8 5/8 csg 4' below GL. Weld on cap. Restore location.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547

Address 620 S. Lincoln, Liberal, Kansas 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Liberal, ss.

Beverly J. Williams, Engineering Technician


(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Beverly J. Williams
Beverly J. Williams, Engineering Tec
(Address) P.O. Box 351, Liberal, KS 67901

SUBSCRIBED AND SWORN TO before me this 26th day of March, 19 90

Cheryl Steers
Notary Public

My Commission Expires:



RECEIVED
STATE CORPORATION COMMISSION
MAR 29 1990
CONSERVATION DIVISION
Wichita, Kansas