

RECEIVED

FEB 24 2003

Well Plugging Record

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

KCC WICHITA

K.A.R. -82-3-117

API NUMBER 15-129-21,478 -00-00
LEASE NAME Ratzlaff A
WELL NUMBER 1-34

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.
4546 Ft. from South Line of Section
1980 Ft. from East Line of Section

LEASE OPERATOR McCoy Petroleum Corporation #5003 SPOT LOCATION 80'S of C NW NE
ADDRESS P. O. Box 780208 Section 34 Township 32 Range 42 W
CITY, STATE, ZIP Wichita, Kansas 67278-0208 County Morton
PHONE # 316-636-2737 Date Well Completed 3/4/97
Character of Well Gas Date Plugging Commenced 12/19/02
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed 12/30/02

The plugging proposal was approved on 12/19/02 (date)
by Steve Durant (KCC District Agent's Name)

Is ACO-1 Filed? yes If not, is well log attached?
Producing Formation(s) Morrow Depth to Top 4906 Bottom 4956 T.D. 5328

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
				8-5/8"	1434	0
				5-1/2"	5328	3041

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Sand at 4860', bail 4 sacks cement. Shot pipe at 3251, 3041' worked free. Pulled to 1460', pump 50 sacks cement with 5 sacks gel. Pull to 500', pump 50 sacks cement. Pull to 40', pump 20 sacks cement. Layed last joint down.

Name of Plugging Contractor Quality Well Service, Inc.
Licence No. 31925
Address 401 W. Main City: Lyons State: KS Zip 67554
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation (Operator)


STATE OF KANSAS COUNTY OF Sedgwick, ss.

Scott Hampel (Employee of Operator or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct so help me God.

(Signature) Scott Hampel
(Scott Hampel, Engineering & Production Manager)

(Address) 453 S. Webb, Suite 310, P.O. Box 780208 City: Wichita State: KS Zip 67278

SUBSCRIBED AND SWORN TO me this 3 day of February, 2003



Karen E. Houseberg
(Notary Public)

My Commission Expires: 9/5/2006



RECEIVED

FEB 24 2003

KCC WICHITA

COPY

SALES OFFICE:
 105 S. Broadway
 Suite #420
 Wichita KS 67202
 (316) 262-3699
 (316) 262-5799 FAX

SALES & SERVICE OFFICE:
 10244 NE Hiway 61
 P.O. Box 8613
 Pratt, KS 67124-8613
 (316) 672-1201
 (316) 672-5383 FAX

ACIDIZING - FRACTURING - CEMENTING

Invoice

Bill to:		5556600	Invoice	Invoice Date	Order	Order Date
MCCOY PETROLEUM			212098	12/31/02	5671	12/30/02
P.O. Box 780208			Service Description			
Wichita, KS 67278-0208			Cement			
			Lease		Well	
			Ratzlaff		A 1-34	
AFE	CustomerRep	Treater	Well Type	Purchase Order	Terms	
	R. McIntire	D. Morris	Old Well		Net 30	

<u>ID.</u>	<u>Description</u>	<u>UOM</u>	<u>Quantity</u>	<u>Unit Price</u>	<u>Price</u>
D203	60/40 POZ (COMMON)	SK	120	\$7.84	\$940.80 (T)
C320	CEMENT GELL	LB	1916	\$0.25	\$479.00 (T)
E107	CEMENT SERVICE CHARGE	SK	120	\$1.50	\$180.00 (T)
E100	HEAVY VEHICLE MILEAGE - 1 WAY	MI	40	\$3.25	\$130.00 (T)
E104	PROPPANT / BULK DELIV SERVICES/TON MILE, \$200 MIN	TM	120	\$1.30	\$156.00 (T)
R400	CEMENT PUMPER, PLUG & ABANDON (Workover Unit) 2 HR	EA	1	\$683.00	\$683.00 (T)

Sub Total:	\$2,568.80
Discount:	\$610.06
Discount Sub Total:	\$1,958.74
Tax Rate: 6.30%	Taxes: \$123.40
(T) Taxable Item	Total: \$2,082.14

PLEASE REMIT TO Acid Services, LLC, Dept No 1131 , Tulsa, OK 74182

Accounts become past due the last day of the month following billing. Interest rate 1.5% per month (18% per year) on past due accounts.

FEB 24 2003



KCC WICHITA

INVOICE NO.

FIELD ORDER

5671

Subject to Correction

CHARGE

Date 12-30-02	Lease RATZLAFF 'A'	Well # 1-34	Legal 34-32-42
Customer ID	County MORSON	State KANSAS	Station PRATT KS
Depth 1460'		Formation	Shoe Joint
Casing 4 1/2"	Casing Depth 1460'	TD	Job Type PTA Old Well
Customer Representative RICHARD MCINTIRE		Treater DICK MOORE	

McCoy Petroleum

AFE Number	PO Number	Materials Received by X [Signature]
------------	-----------	--

Product Code	QUANTITY	MATERIAL, EQUIPMENT and SERVICES USED	UNIT PRICE	AMOUNT	ACCOUNTING	
					CORRECTION	AMOUNT
D203	120 SK	60/40 Poz (COMMON)	✓			
C320	416 lb	CEMENT GEL	✓			
C320	1500 lb	CEMENT GEL	✓			
E107	120 SK	CEMENT SERVICE CHARGE				
E100	1 UNIT	UNITS 1EA MILES 40 miles				
E104	120 SK	TONS MILE 208 MILES 40 miles				
R400	1 pump	EA. 1 UNIT PUMP CHARGE PTA				
DISCOUNT TOTAL						
PLUS TAX						
						1958.74

10244 NE Hiway 61 · P.O. Box 8613 · Pratt, KS 67124-8613 · Phone (620) 672-1201 · Fax (620) 672-5383 TOTAL

RECEIVED

FEB 24 2003

KCC WICHITA



TREATMENT REPORT

Customer ID		Date	
Customer <i>McCoy Petroleum</i>		<i>12-30-02</i>	
Lease <i>RATZLAFF 'A'</i>		Lease No.	Well # <i>1-34</i>
Field Order # <i>5671</i>	Station <i>Pratt, KS</i>	Casing <i>4 1/2"</i>	Depth <i>1460'</i>
Type Job <i>Plug to Annulus</i>		County <i>Marion</i>	State <i>KS</i>
Formation		Legal Description <i>34-32-92</i>	

PIPE DATA		PERFORATING DATA		FLUID USED		TREATMENT RESUME		
Casing Size <i>4 1/2"</i>	Tubing Size	Shots/Ft <i>60/40 por</i>		Acid		RATE	PRESS	ISIP
Depth <i>1460'</i>	Depth	From <i>50SK</i>	To <i>1460'</i>	Pre Pad		Max <i>6</i>	<i>150</i>	5 Min.
Volume <i>23.2</i>	Volume	From <i>50SK</i>	To <i>500'</i>	Pad		Min <i>4</i>	<i>0</i>	10 Min.
Max Press	Max Press	From <i>20SK</i>	To <i>40'</i>	Frac		Avg <i>4</i>	<i>150</i>	15 Min.
Well Connection	Annulus Vol.	From	To			HHP Used		Annulus Pressure
Plug Depth	Packer Depth	From	To	Flush <i>H2O Fresh</i>		Gas Volume		Total Load

Customer Representative	Station Manager <i>DAVE AGENCY</i>	Treater <i>Dirk Moeck</i>	
Service Units	<i>#112</i>	<i>#27</i>	<i>#36-70</i>

Time	Casing Pressure	Tubing Pressure	Bbls. Pumped	Rate	Service Log
<i>1350</i>					<i>ON LOCATION</i>
<i>1430</i>					<i>SAFETY MEETING</i>
<i>1456</i>	<i>100</i>		<i>0</i>	<i>4</i>	<i>LOAD HOLES w/CEL H2O</i>
<i>1505</i>	<i>100</i>		<i>45</i>	<i>6</i>	<i>START FRESH H2O</i>
<i>1510</i>			<i>67</i>	<i>4</i>	<i>HOLES FULL</i>
<i>1515</i>	<i>100</i>		<i>0</i>	<i>4-</i>	<i>START 1st plug 50SK @ 1460'</i>
<i>1520</i>	<i>100</i>		<i>9.6</i>	<i>4</i>	<i>FLUSH</i>
<i>1523</i>	<i>100</i>		<i>22</i>		<i>SHUT DOWN</i>
<i>1556</i>	<i>100</i>		<i>0</i>	<i>4</i>	<i>START 2nd Aug 50SK @ 500'</i>
<i>1600</i>	<i>100</i>		<i>9.6</i>	<i>4</i>	<i>FLUSH</i>
<i>1601</i>	<i>100</i>		<i>13</i>		<i>SHUT DOWN</i>
<i>1622</i>	<i>100</i>		<i>0</i>	<i>4</i>	<i>START 3rd plug 20SK @ 40'</i>
<i>1623</i>	<i>100</i>		<i>3.5</i>	<i>4</i>	<i>FLUSH</i>
<i>1624</i>	<i>100</i>		<i>5</i>		<i>SHUT DOWN</i>
					<i>JOB COMPLETE</i>
					<i>THANK YOU FOR CALLING ACID SERVICES</i>
					<i>Dirk / CURRAN / MATT</i>