


15-129-00063-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Morton County. Sec. 28 Twp. 32S Rge. 41 (E) W (W)
Location as "NE/CNW/SW" or footage from lines C SE/4
Lease Owner Graham-Michaelis Drilling Company
Lease Name Dewell Well No. 1
Office Address 211 North Broadway, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 13 19 59
Application for plugging filed June 18 19 59
Application for plugging approved June 13 19 59
Plugging commenced June 13 19 59
Plugging completed June 14 19 59
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production none 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Depth to top Bottom Total Depth of Well 2270 KB Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				7"	2262.65 GL	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mixed 10 sacks of cement and placed on bottom to plug hole. Pumped 50 barrels of rotary mud in hole, made bridge plug and stopped at 600'. Mixed 10 sacks cement and poured in hole, made bridge plug at 50' and mixed 10 sacks cement. Top of cement 4' below ground level.

RECEIVED
STATE CORPORATION COMMISSION

JUN 20 1959

CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUN 20 1959

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graham-Michaelis Drilling Company
Address 211 North Broadway, Wichita 2, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK ss.
John L. James - Geologist (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John L. James John L. James
211 North Broadway, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of June, 19 59

My commission expires May 24, 1961

Mildred A. Fisher
Mildred A. Fisher Notary Public.

PLUGGING
FILE SEC 28 T. 32 R. 41W
BOOK PAGE 46 LINE 31

DEWELL # 1

WELL RECORD:

LOCATION:

C SE/4 Sec. 28-T32S-R41W
Morton County, Kansas

Commenced: 4/17/59
Completed: 4/24/59
(Rotary)

CONTRACTOR:

Graham-Michaelis Drilling Company
211 North Broadway
Wichita 2, Kansas

CASING RECORD:

73 Joints 7" - 20# Used Casing
cemented 1st Stage w/1300 sx
common - cemented 2nd Stage
w/200 sx common 2%

	<u>LOG</u>	
Surface Clay & Sand	0 -	213
Red Bed & Sand	213 -	665
Red Bed, Shale & Sand	665 -	980
Shale, Shells & Red Bed	980 -	1020
Red Bed & Gyp	1020 -	1100
Sand & Lime	1100 -	1365
Lime & Shale	1365 -	1655
Lime	1655 -	1756
Lime & Shale	1756 -	2205
Lime, Shale & Sand	2205 -	2270

2270' Total Rotary Depth

The undersigned, Graham-Michaelis Drilling Company, hereby certifies that the above is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Report.

Graham-Michaelis Drilling Company

By John L. Jensen
Geologist

RECEIVED
STATE CORPORATION COMMISSION

JUN 19 1959

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE <u>SEC 28 T 32 R 41W</u>
BOOK <u>PAGE 46</u> LINE <u>31</u>