

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-129-20,805-000

LEASE NAME Berryman Richfield

WELL NUMBER 8-1

1980 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 35 TWP. 32S RGE. 41 (E) or (W)

COUNTY Morton

Date Well Completed 5-16-86

Plugging Commenced 5-16-86

Plugging Completed 5-16-86

LEASE OPERATOR Ladd Petroleum Corporation

ADDRESS 370 17th St., Suite 1700, Denver, CO 80202

PHONE#(303) 620-0100 OPERATORS LICENSE NO. 6029

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes If not, is well log attached? Sent under separate cover

Producing Formation Morrow Depth to Top 4994 Bottom 5000 T.D. 5090

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Morrow Sand	Water	4994	5000	8 5/8	1411	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Hole was full of mud prior to plugging. Cement plugs of 60/40 poz + 6% gel as follows:

5035 - 4935	35 sxs	600--	500	30 sxs
2650 - 2450	100 sxs	40 -	0	10 sxs
1440 - 1340	50 sxs	Rathole		10 sxs

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Dowell License JUN 17 1986

Address Box 887, Ulysses, Kansas 67880

STATE OF COLORADO COUNTY OF DENVER, ss.

Michael A. Tornes (Employee of Operator) or ~~XXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, as filed that the same are true and correct, so help me God.

(Signature) Michael A. Tornes

(Address) 370 17th St. Suite 1700
Denver, Colorado 80202

SUBSCRIBED AND SWORN TO before me this 9th day of June, 19 86.

My Commission Expires: December 27, 1988
Notary Public

