

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Stevens SEC. 23 TWP. 32S RGE. 38 W
 Location as in quarters or footage from lines:
C W/2 SE/4

	2B		

Lease Owner Anadarko Production Company
 Lease Name Nordling "A" Well No. 1
 Office Address Box 351, Liberal, Kansas 67901
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry
 Date Well Completed 6/28/82
 Application for plugging filed 7/13/82
 Plugging commenced 6/29/82
 Plugging completed 6/29/82
 Reason for abandonment of well or producing formation Dry

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas

Producing formation _____ Depth to top _____ bottom _____ T.D. 6225

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8	1768	0

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set. Spotted 25 sxs cmt @ 3200', 25 sxs @ 2800', 50 sxs
@ 1700', 25 sxs @ 800', 10 sxs 40'-0', 10 sxs in rathole and mousehole. Heavy drilling
mud was pumped between each plug. Completed ^{RECEIVED} pm, 6/29/82.

STATE CORPORATION COMMISSION

JUL 15 1982

CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.

STATE OF Kansas COUNTY OF Seward, ss.

Paul Campbell (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) Paul Campbell
Box 351, Liberal, Kansas 67901
 (Address)

SUBSCRIBED AND SWORN TO before me this 14th day of July, 19 82

My Commission expires:

STATE NOTARY PUBLIC
 ELIZABETH J. HOOPER
 Seward County, Kansas
 My Appt. Expires 7-26-83

Elizabeth J. Hooper
 Notary Public.

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

Nordling "A" #1
C-W/2-SE Sec 23-32S-38W
Stevens County Kansas

Commenced: 6-10-82

Completed: 6-29-82

OPERATOR: ANADARKO PRODUCTION CO.

Depth		Formation	Remarks
From	To		
0	370	Surface Clay-Sand	
370	985	Redbed-Sand	Ran 41 jts of 8 5/8" 24/
985	1520	Sand-Redbed-Anhy	csg set @ 1768' Cemented
1520	1774	Sand-Redbed	w/600 sks Posmix 4% Gel
1774	1935	Anhy-Lime-Shale	2% CC + 200 sks Common
1935	2555	Lime-Shale	2% CC PD @ 5:00 p.m.
2555	2918	Core	6-11-82
2918	6225	Lime-Shale	
	6225 - TD		DRY & ABANDONED

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above Drillers' Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton II
JAMES S. SUTTON II

Subscribed and sworn to before me this 7th day of July, 1982.

Elizabeth J. Edwards
ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1983.

STATE OF KANSAS
NOTARY PUBLIC
ELIZABETH J. EDWARDS