

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-189-21362-0000

LEASE NAME Warren Moon

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1
1390 Ft. from S Section Line

3890 Ft. from E Section Line

SEC. 26 TWP. 32S RGE. 38 (E) or (W)

COUNTY Stevens

Date Well Completed 8/6/89

Plugging Commenced 8/6/89

Plugging Completed 8/6/89

LEASE OPERATOR Mobil Oil Corporation

ADDRESS P. O. Box 5444, Denver, CO 80217

PHONE# (303) 298-2069 OPERATORS LICENSE NO. 5208

Character of Well Dry

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on August 6, 1989 (date)

by Dwayne Rankin, Dodge City, Kansas (KCC District Agent's Name).

Is ACO-1 filed? Attached If not, Is well log attached? yes

Producing Formation Target Upper Morrow Depth to Top 5688' Bottom 6123' T.D. 6500'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		Surf	1753	8-5/8"	1757	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Cement Mix: 60:40 Poz + 6% Gel

Plug #1 - 2900'-2400', 150 sx; Plug #2 - 1800'-1600', 50 sx; #3 - 900'-700', 40 sx; #4 - 40'-6', 10 sx; 15 sx in rathole; 15 sx in mousehole.

(If additional description is necessary, use BACK of STATE FORM 112)

Name of Plugging Contractor Halliburton

Address P. O. Box 1598, Liberal, KS 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mobil Oil Corp., 123 East 11th, Liberal, KS 67901

STATE OF Colorado COUNTY OF Denver, ss.

B. R. Maynard

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) W.E. Ward for B.R. Maynard
Regulatory Compliance Manager

(Address) P. O. Box 5444, Denver, CO 80217

SUBSCRIBED AND SWORN TO before me this 13th day of October, 19 89

My Commission Expires: 1/3/91

Jayce George
Notary Public