

API NUMBER 15-189-9223180000

LEASE NAME MLP Curtis A

WELL NUMBER 1

2203.3 Ft. from S Section Line

1407.7 Ft. from E Section Line

SEC. 6 TWP. 32 RGE. 38 (X) of (W)

COUNTY Stevens

Date Well Completed 11-13-99

Plugging Commenced 3-13-00

Plugging Completed 3-15-00

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Oxy USA Inc.

ADDRESS 1701 N Kansas Liberal KS

PHONE# (316) 629-4200 OPERATORS LICENSE NO. 5447

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-13-00 (date)

by Gary Winters (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? \_\_\_\_\_

Producing Formation Lower Morrow Depth to Top 5879 Bottom 5892' T.D. 6300'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				<u>8 5/8</u>	<u>1492</u>	<u>-</u>
				<u>5 1/2</u>	<u>6292</u>	<u>1906</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other p were used, state the character of same and depth placed, from feet to feet each :  
Mixed 3 sx hulls & 25 sx cnt. to plug perfs from 5879 to 5679  
Rec. 1906 5 1/2. Pull to 1525. Attempt to circ. hole w/mud. Mixed 65 sx plug @  
1525. Pull to 500. Mixed 50 sx plug from @ 500. Wait overnight. Tag top  
of plug @ 489. Load hole w/mud to 40. 10 sx plug 40 to 0. Cut off & cap 8 5/8  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent Casing Pulling Service License No. 6547

Address PO Box 506 Liberal KS 67905

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oxy USA Inc.

STATE OF Kansas COUNTY OF Seward, ss.

Kenny L. Andrews (Employee of Operator) or (Operator above-described well, being first duly sworn on oath, says: That I have knowledge of the fa. statements, and matters hereinafter stated and the log of the above-described well as filed the same are true and correct.  
STATE CORPORATION COMMISSION

(Signature) Kenny Andrews

(Address) PO Box 2528 Liberal, KS. 67905

MAR 22 2000

NOTARY PUBLIC, State of Kansas  
ANITA PETERSON  
My Appt. Exp. Oct 1, 2001

SUBSCRIBED AND SWORN TO before me this 21<sup>st</sup> day of March, 2000

Wichita, Kansas  
Anita Peterson  
Notary Public

My Commission Expires: Oct 1, 2001