

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

#3-32-1998

RECEIVED
KANSAS CORP COM.

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

RECEIVED
KANSAS CORP
FORM CP-1 (3/92)

API # AS 19-201150001 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Marlin Oil Corporation KCC LICENSE # 9228
(owner/company name) (operator's)

ADDRESS P. O. Box 14630 CITY Okla. City

STATE OK ZIP CODE 73113-0630 CONTACT PHONE # (405) 478-1900

LEASE Wendell WELL# 1 SEC. 10 T. 34S R. 30 (East/West)

SW NW SPOT LOCATION/QQQQ COUNTY Meade

1980 FEET (in exact footage) FROM S (N) (circle one) LINE OF SECTION (NOT Lease Line)

660 FEET (in exact footage) FROM E (W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 1524 CEMENTED WITH 650 SACKS

PRODUCTION CASING SIZE 4 1/2 SET AT 6120 CEMENTED WITH 225 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Perfs: 5860-88'; 5920-26'; 6022-32'

ELEVATION 2720/2725 T.D. 6200 PBTD 5912 ANHYDRITE DEPTH 1650
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set CIBP at 5830', load hole with 9 ppg mud, cut off 4 1/2" csg + 2700'. Spot 50 sx cement plug from 530-630'. Spot 10 sx cement plug from 34-4'. Cut off 4' below ground level and cap with steel I.D. plate.
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Dick Lynn PHONE# (405) 478-1900

ADDRESS P. O. Box 14630 City/State Okla. City, OK 73113-0630

PLUGGING CONTRACTOR Sargent's Casing Pulling Service KCC LICENSE # 6547
(company name) (contractor's)

ADDRESS P. O. Box 506, Liberal, KS 67905 PHONE # (313) 624-7455

PROPOSED DATE AND HOUR OF PLUGGING (If known?) _____

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 3-30-98 AUTHORIZED OPERATOR/AGENT: [Signature]
(signature)



BRAND X PERFORATORS,
 GAMMA RAY - CEMENT
 BOND LOG

15-119-20115-0001

COMPANY MARLIN OIL COR. WELL WENDELL NO. 1 FIELD S.W. NOVINGER CNTY MEADE STATE KS	COMPANY <u>MARLIN OIL CORP.</u>
	WELL <u>WENDELL NO. 1</u>
	FIELD <u>S.W. NOVINGER</u>
	COUNTY <u>MEADE</u> STATE <u>KANSAS</u>
LOCATION: <u>C-SW-NH</u>	
SEC. <u>10</u> TWP. <u>34S</u> RGE. <u>30W</u>	
PERM. DATUM <u>GROUND LEVEL</u> ELEV. <u>2720</u>	
LOG MEASURED FROM <u>KB 12</u> FT. ABOVE PERMANENT DATUM	
DRILLING MEASURED FROM <u>KB</u>	
ELEV. : K.B. <u>2732</u>	
D.F. <u>2730</u>	
G.L. <u>2720</u>	

DATE	<u>11-29-95</u>
RUN NO.	<u>ONE</u>
DEPTH DRILLER	<u>6200</u>
DEPTH LOGGER	<u>6059</u>
BTM LOG INTERVAL	<u>6055</u>
TOP LOG INTERVAL	<u>5100</u>
OPEN HOLE SIZE	<u>7.875</u>
TYPE FLUID	<u>WATER</u>
DENS. VISC.	
MAX REC. TEMP. °F.	<u>131</u>
EST. CEMENT TOP	
TIME WELL READY	
TIME LOGGER ON BTM	
EQUIP. NO.	<u>139</u>
LOCATION	<u>WOODWARD, OK</u>
RECORDED BY	<u>DONCARLOS</u>
WITNESSED BY	<u>MR. RUSSELL</u>

BOREHOLE RECORD				TUBING RECORD			
RUN NO.	BIT	FROM	TO	SIZE	HGT.	FROM	TO
CASING RECORD		SIZE	MT/FT	GRADE	TYPE JOINT	TOP	BOTTOM
SURFACE STRING		<u>8.625</u>				<u>SURF.</u>	<u>1524'</u>
PROD. STRING		<u>4.5</u>				<u>SURF.</u>	<u>TD</u>
LINER							



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Susan M. Seltsam, Commissioner Cynthia L. Claus, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

April 6, 1998

Marlin Oil Corporation
P O Box 14630
Oklahoma City OK 73113-0630

Wendell #1
API 15-119-20,115-0001
1980 FNL 660 FWL
Sec. 10-34S-30W
Meade County

Dear Dick Lynn,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-6760