

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 119-20,708-0000 (of this well).
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Kaiser-Francis Oil Company OPERATOR'S LICENSE NO. 6568 6-93

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468 PHONE # (918) 491-4314

LEASE (FARM) Lester Davis WELL NO. 1-31 WELL LOCATION NW NW SE COUNTY Meade

SEC. 31 TWP. 32S RGE. 28 (E) or (W) TOTAL DEPTH 5800 PLUG BACK TD 5733

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8 5/8 SET AT 1400 CEMENTED WITH 750 SACKS

CASING SIZE 4 1/2 SET AT 5797 CEMENTED WITH 100 SACKS

PERFORATED AT 5557-5562

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set cement plugs as directed by the KCC district office.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN To be scheduled upon approval

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE
RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: RECEIVED
Phil Goodwin, Supt. PHONE # (806) 435-6670 STATE CORPORATION COMMISSION

ADDRESS P. O. Box 746, Perryton, TX 79070

PLUGGING CONTRACTOR Sargent's Casing Pulling Service LICENSE NO. 6547 NOV 30 1992

ADDRESS P. O. Box 506, Liberal, KS 67901 PHONE # (316) 624-7455

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: C. Jan Valkenburg
(Operator or Agent)
Charlotte Van Valkenburg

DATE: 11/24/92

GABBERT-JONES, INC.
DRILLERS WELL LOG

LESTER DAVIS #1-31
NW NW SE
Sec. 31-32S-28W
Meade County, Kansas

Commenced: 4-24-85

Completed: 5-7-85

Operator: KAISER-FRANCIS OIL COMPANY

Depth		Formation	Remarks
From	To		
0	50	Cased hole	50' of 20" csg
50	330	Sand	
330	385	Redbed-Sand Streaks	
385	940	Redbed	Ran 34 jts of 24# 8 5/8"
940	1175	Gloritta	csg set @ 1400 W/550 sks
1175	1300	Shale-Sand	Light - 1/4# Floseal - 2% CC
1300	1405	Shale	200 sks Class H - 3% CC
1405	1745	Anhy-Sand-Lime	PD @ 11:15AM 4-26-85
1745	2523	Sand-Shale	
2523	2700	Lime-Shale	
2700	2929	Sand-Shale	Ran 138jts of 10 1/2#
2929	3100	Shale-Lime	4 1/2" csg set @ 5797'
3100	3580	Lime-Shale	cemented W/100 sks
3580	3805	Shale-Lime	Thickset PD @ 4:00AM
3805	4105	Lime-Shale	5-7-85
4105	4275	Shale-Lime	
4275	4930	Lime-Shale	
4930	5065	Lime	
5065	5145	Lime-Shale	
5145	5360	Lime	
5360	5450	Lime-Shale	
5450	5664	Lime	
5664	5764	Lime-Shale	
5764	5800	Lime	

5800-TD

State of Kansas)
County of Sedgwick) I, the undersigned, being duly sworn on oath, state
that the above Drillers' Well Log is true and correct
to the best of my knowledge and belief and according
to the records of this office.

GABBERT-JONES, INC.


James S. Sutton, II -- President

Subscribed & sworn to before me this
9 day of May, 19 85.


Lola Lenore Costa

My Commission expires November 21, 1988

Joan Finney
Governor

Jim Robinson
Chairman

F. S. Jack Alexander
Commissioner

Rachel C. Lipman
Commissioner

Judith McConnell
Executive Director

Brian Moline
General Counsel



Kansas Corporation Commission

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

December 3, 1992

Kaiser-Francis Oil Co.
Box 21468
Tulsa OK 74121-1468

Lester Davis 1-31
API 15-119-20,708
NW NW SE
Sec. 31-32-28W
Meade County

Dear Charlotte Van Valkenburg,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams
Production Supervisor

Conservation Division
William R. Bryson
Director
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, Kansas 67202-1286
Telephone (316) 263-3238

District: #1 304 W. McArtor
Dodge City, KS 67801
(316) 225-6760