



15451-19109-0000

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM

(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 2 1962

CONSERVATION DIVISION
Wichita, Kansas

10-2-1962

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

I have this date Sept 28, 1962, 1962, authorized
the following plugging operation:

Operator's full Name: Amerada Petroleum Corp.Complete Address: Box 197 Great Bend, Kansas.Lease Name: Mary Moore #1 Well No. #1Location: C-NW NE NE Sec. 31 Twp. 28S Rge. 13 (E) (W) XCounty Pratt Total Depth 4568'Oil Well Gas Well Input Well SWD Well D & A XOther well as hereafter indicated:

Operator was instructed to plug well as follows:

355' of 8 5/8" circulated with cement. Hole filled to
250' with heavy drill mud, 1 sack hulls, 1st cementing plug
and 20 sacks cement. Hole filled to 35' with heavy drill
mud, 1 sack hulls, 2nd cementing plug and 10 sacks cement
to base of cellar. Rat hole bridged and 2 sacks cement.

Very truly yours,

Herbert J. Gustus
Conservation Division Agent