

State of Kansas



15-151-20321-6600

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

WICHITA, KANSAS

New Address  
245 North Water  
Wichita, Kansas 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

FEB 23 1976

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

2-23-1976

Dear Sir:

Mr. Crowe of DaMac Drlg Co has this

date requested permission to plug the following described well:

Mr. Crowe guarantees payment of the plugging fee.

Operator's full Name: Petrie Exploration Corp

Complete Address: Rt 1 Pratt, KS

Lease Name: Aenchbacher Well No. 1

Location: SW/NE/NE Sec. 21 Twp. 28s Rge. 13 (E) (W)

County: Pratt Total Depth 3146 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Crowe was instructed to plug the well as follows:

215 ft 8 5/8 surface cemented with 250 sacks. Pump plug,

35 sacks cement to 200 ft. Mud to 40 ft, plug, 1/2 sack

hulls, 15 sacks cement to surface. 2 sacks cement in rat

hole, 2 in mouse hole.

Pumped by Allied Cementing Great Bend, KS

Very truly yours,

*Russell Beaman*  
Conservation Division Agent