



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission
 CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

15-095-00501-0000

RECEIVED
 STATE CORPORATION COMMISSION

DEC 16 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

12-16-1963

Dear Sir:

Mr. Vaughn Francis of Terrel Drilling & Prod. has this date requested permission to plug the following described well:

Mr. Francis guarantees payment of the plugging fee.

Operator's full Name: Fred B. & Phillip F. Anschutz

Complete Address: 1521 Wichita Plaza, Wichita, Kansas

Lease Name: Adelhardt Well No. # 1

Location: C SW NE Sec. 36 Twp. 28 Rge. 10 (E) (W) W

County Kingman Total Depth 4670 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Francis was instructed to plug the well as follows:

230' of 8 5/8" surface pipe, cemented with 175 sacks.
Fill hole with drilling mud to 250', 1st cementing plug,
bridge with hulls, cement with 25 sacks. Fill hole with
drilling mud to 40', 2nd cementing plug, bridge with hulls,
cement with 10 sacks to base cellar. Bridge and cement rat
hole with 2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent