



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

15-095-01237-0000

FEB 11 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Jack Kaiser of German Drilling Co. has this date requested permission to plug the following described well:

Mr. Jack Kaiser guarantees payment of the plugging fee.

Operator's full Name: German Drilling Co.

Complete Address: 608 Petroleum Bldg., Wichita, Kansas

Lease Name: Cooley Estate Well No. # 1

Location: C NW/4 NW/4 Sec. 2 Twp. 28S Rge. 10 (E) (W) W

County Kingman Total Depth 4489 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Kaiser was instructed to plug the well as follows:

245' of 8 5/8" surface pipe circulated with 200 sacks
Cement. Fill hole with heavy mud to 180', 1/2 sack hulls,
1st cementing plug, cement with 20 sacks. Fill hole with mud
to 40', 1/2 sack hulls. 2nd cementing plug, cement with
10 sacks to base of cellar. Rat hole bridged and cemented
with 2 sacks

Very truly yours,

Archie Elving
 Conservation Division Agent