

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-189-21,301-0000

LEASE NAME Lightfire

WELL NUMBER 1-24

4620 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 24 TWP. 32S RGE. 36W (E) or (W)

COUNTY Stevens

Date Well Completed \_\_\_\_\_

Plugging Commenced 4/11/89

Plugging Completed 4/12/89

TYPE OR PRINT

NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Dantex Oil & Gas, Inc.

ADDRESS 4321 No. Central Expwy., Dallas, TX 75205

PHONE#(214) 528-8127 OPERATORS LICENSE NO. 30026

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4:40 PM 4/11/89 (date)

by Dan Goodrow (316) 225-6760 (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? \_\_\_\_\_

Producing Formation None Depth to Top - Bottom -

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS \_\_\_\_\_ CASING RECORD \_\_\_\_\_

Formation	Content	From	To	Size	Put in	Pulled out
		1820' KB	0	8-5/8	1807'	Cut off 3'
		42'	0	16"	42'	Cut off 3'

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUN 19 1989  
 CONSERVATION DIVISION  
 Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.  
9.0 ppg mud from TD (6600') to surface. Circ w/rig pump. Spotted cement plugs thru open ended drill pipe as follows: 2900' up 100 sx, 60/40 Poz w/6% gel. 1830' up 50 sx of same slurry. 800' up 40 sx same slurry. 40' to surface 10 sx. Plugged rat & mouse holes w/25 sacks same slurry. Cut 8-5/8" and 16" csg off 3' below GL. Welded on plate w/marker.  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gabbert-Jones, Inc. License No. 5852

Address 333 E. English, Suite 215, Wichita, Kansas 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Paid by Dantex Oil & Gas, Inc.

STATE OF Texas COUNTY OF Dallas, ss.

Cecil D. Gritz (Employee of Operator) ~~XXXXXXXXXXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Cecil D. Gritz

(Address) 4321 N. Central Expressway, Dallas, TX

75205

SUBSCRIBED AND SWORN TO before me this 14th day of June, 1989

Dandra Ricks  
 Notary Public

My Commission Expires: 12/-3/91