

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

Well was completed on  
API NUMBER 7-27-55

15-119-10235-0000

LEASE NAME Novinger

TYPE OR PRINT

WELL NUMBER 1001 W

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

4620 Ft. from S Section Line

660 Ft. from E Section Line

LEASE OPERATOR OXY USA Inc.

SEC. 3 TWP. 34S RGE. 30 (E or W)

ADDRESS 3543 N.W. 58th Street, Oklahoma City, OK 73112

COUNTY Meade

PHONE# (405) 949-4268 OPERATORS LICENSE NO. 5447

Date Well Completed 7-27-55

Character of Well Oil

Plugging Commenced 2-15-88

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2-19-88

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Glenn Barlow, District #1

Well was completed on

Is ACO-1 filed? 7-27-55 If not, is well log attached? yes

Producing Formation 5290-96' Depth to Top 5290' Bottom 5296' T.D. 5380'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Marmaton	Oil	5290	5296	13 3/8	723	none
				9 5/8	2707	1217
				5 1/2	5380	2810

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

CMP @ 5100 w/ 2 sks. of cement Pump 50 sks. of cement to plug bottom of 9 5/8 plug @ 2740 to 2640 Pump 50 sks. of cement to plug bottom of 13 3/8 plug from 750 to 650  
Put 20 sks. of cement from 40 to 0

Cut off & cap 13 3/8 3' below ground level. KCC Witness: Mr. Glenn Barlow  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address Box 506 Liberal, Kansas 67905-0506

STATE OF Kansas COUNTY OF Seward, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct. So help me God.

STATE CORPORATION COMMISSION

(Signature) Bryan D. Humphries  
Bryan Humphries

(Address) Engineering Manager  
3543 N.W. 58th Street, OKC, OK

APR 14 1988  
4-12-1988  
SUBSCRIBED AND SWORN TO before me this 5th day of April, 19 88

CONSERVATION DIVISION  
Wichita, Kansas

Joanne S. Porter  
Notary Public

My Commission Expires: 6-12-88