

15-119-00034-0001

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Meade County. Sec. 3 Twp. 33 Rge. (E) 30 (W)
Location as "NE/CNW&SW" or footage from lines C - NE - NW
Lease Owner James Donoghue
Lease Name Klein Well No. 1
Office Address
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 1 - 18 1957
Plugging completed 1 - 22 1957
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merle Rives
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1600	None
				5 1/2	5846	2833.51

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Top of cement inside casing at 4632' - all perforations cemented off - pulled pipe part of way out - pumped hole full of Jell mud - finished pulling casing - mudded hole to 600' - set plug & dumped 20 sks cement @ 600' - mudded to 35' - set rock bridge - dumped 10 sks cement to base of cement.

RECEIVED
STATE CORPORATION COMMISSION

FEB - 9 1957

CONSERVATION DIVISION
Wichita, Kansas

2-9-1957

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R & D Casing Pulling Company License 236
Address Box 569 Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF FINNEY, ss.
R. W. Lange (employee of owner) or (owner/operator) of the above-described well, being first duly sworn to, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) R. W. Lange
Box 134, Garden City, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 4th day of February, 1957

Darlene Brady
Notary Public.

My commission expires August 13, 1960

24-7368-5 3-53-20M





DRILLING COMPANY, INC. Phone 3-1279 352 N. BROADWAY WICHITA, KANSAS

James Donoghue
#1 Klein
C NE/4 NW/4 Section 3-34-30W
Meade County, Kansas

Mr. James Donoghue
Denver Club Building
Denver, Colorado

Elevation:

Spudded:

Rotary Completed:

Contractor:

April 2, 1956

April 29, 1956

Rocket Drilling Company, Inc.

CASING RECORD

1455' 8-5/8" O.D. 24# seamless casing cemented with 650 sacks cement.
5846' 5-1/2" O.D. 14# seamless casing cemented with 250 sacks cement.

DRILLERS LOG

Clay	0 to 520	Lime	314.3
Shale & Shells	555	Lime & Shale	3230
Sand, Rock & Clay	760	Shale & Lime	3380
Red Bed	875	Chaiky Lime & Shale	3525
Anhydrite	920	Chalk & Lime	3610
Red Bed & Sand	1190	Lime & Shale	3830
Anhydrite & Sand	1275	Shale & Lime	4006
Shale & Shells	1405	Lime & Shale	4071
Sand	1425	Shale	4235
Shale & Sand	1440	Shale & Lime	4379
Anhydrite	1455	Lime & Shale	4485
Anhydrite & Shale	1575	Lime	4532
Salt & Sand	1660	Shale & Lime	4605
Shale	1900	Lime	4652
Shale & Shells	2110	Lime & Shale	4741
Anhydrite & Shale	2315	Lime	5125
Lime & Shale	2875	Lime & Sand	5181
Shale & Lime	2958	Lime & Shale	5230
Lime & Shale	3088	Lime	5846 T.D.

RECEIVED
STATE CORPORATION COMMISSION

FEB - 9 1957

STATE OF KANSAS)

COUNTY OF SEDGWICK)

SS

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that to the best of my knowledge and belief the foregoing log is true and correct.


ROCKET DRILLING COMPANY, INC.

L. H. Myrick
L. H. Myrick

Subscribed and sworn to before me, a Notary Public, in and for the County and State aforesaid, this 30th day of April, 1956.

My commission expires:

10/28/1959



Notary Public