

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Meade County, Sec. 10 Twp. 34S Rge. (E) 30W(W)

Location as "NE/CNW/SE/SW" or footage from lines: C SW NW
Lease Owner: Hickerson Oil Co.
Lease Name: Wendell Fox Well No. 1
Office Address: 2420 Western Federal Savings Bldg., Denver, Col
Character of Well (completed as Oil, Gas or Dry Hole): Dry Hole
Date well completed: September 13, 1972
Application for plugging filed: 19__
Application for plugging approved: 19__
Plugging commenced: September 13, 1972
Plugging completed: September 13, 1972
Reason for abandonment of well or producing formation: Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production: 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Edgar Eves of Sublette)

Name of Conservation Agent who supervised plugging of this well: _____
Producing formation: _____ Depth to top: _____ Bottom: _____ Total Depth of Well: 6200 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface Casing	0	1524'	8-5/8"	1524'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy Mud from Total Depth to 1200 Feet,
35 sax Cement to 1100 Feet; Mud to 45 Feet,
1/2 sax Halls, Plug Bridged and 15 sax Cement
to Base of Cellar; 2 sax Cement in Rat Hole.
Job completed @ 2:30 A.M. by HOWCO.


RECEIVED
STATE CORPORATION COMMISSION
SEP 19 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor: Halliburton
Address: P. O. Box 129, Liberal, Kansas 67901

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Clarence Michael of Sage Drilling Co. (employee of owner) of the above described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Clarence Michael
500 Bitting Building, Wichita, Kansas
(Address)



Sworn to before me this 18th day of September, 1972.

(Signature) Louise K. Whitted
Louise K. Whitted - Notary Public

November 26, 1974.
My commission expires

DRILLERS LOG

WENDELL FOX NO. 1

CASING RECORD:	OPERATOR: Hickerson Oil Co.	DESCRIPTION:
8-5/8" @ 1524' w/650 sax cement	CONTRACTOR: Sage Drilling Co.	C SW NW Sec. 10-34S-30W Meade County, Kansas
TOTAL DEPTH: 6200'	COMMENCED: August 31, 1972	
	COMPLETED: September 13, 1972	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Sand & Clay	0	330	
Sand, Shale & Gyp	330	1100	
Red Bed	1100	1447	
Anhydrite	1447	1590	
Shale & Lime	1590	2555	
Lime & Shale	2555	5906	
Lime, Shale & Sand	5906	5993	
Lime & Shale	5993	6200	D&A

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

BY Clarence Michael
Clarence Michael



Subscribed and sworn to before me this 18th day of September, 1972.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1974.

RECEIVED
STATE CORPORATION COMMISSION
SEP 19 1972
CONSERVATION DIVISION
Wichita, Kansas